

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**

URBAN  
 ← 90% FEDERAL 20% STATE →  
 0005 0005 0004  
 3P 3P 3R

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 3P	0005 3P	0004 3R
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	10799	3710	845	6244
20800150	TRENCH BACKFILL	CUYD	184			184
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	8.7			8.7
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	46.9	34.5	4.8	7.6
40600300	AGGREGATE (PRIME COAT)	TON	224.8	165.5	23.1	36.2
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	8742.4	6179.7	862.7	1700.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	16,363.6	12,543.5	2,750.9	1,069.2
40600990	TEMPORARY RAMP	SQ YD	1,334.6	890.8	207.3	236.5
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	12592.1	9269.5	1294	2028.6
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	63.85	56.67	7.18	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1966.5	1415.9	273	277.6
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	1355	510	845	
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	9444	3200		6244
42001200	PAVEMENT FABRIC	SQ YD	1355	510	845	
42001300	PROTECTIVE COAT	SQ YD	7950	7395.6	554.4	
44000100	PAVEMENT REMOVAL	SQ YD	7,580	4,555		3025
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	4431	4431		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9981	4120	550	5311
44003100	MEDIAN REMOVAL	SQ FT	51950	16850	3800	31300
44022025	PARTIAL DEPTH REMOVAL 2"	SQ YD	7,446.1	5,385.6	673.3	1,387.2
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	13.3	13.3		
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	72	72		
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	653.3	653.3		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	522.7	32	240	250.7
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	80		48	32
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	53.4			53.4
44201299	DOWEL BARS 1 1/2"	EACH	1360	80	660	620
44213000	PATCHING REINFORCEMENT	SQ YD	738.6	738.6		
44213200	SAW CUTS	FOOT	5416	2164	1632	1620
44213202	TIE BARS 1"	EACH	3393	178		3215
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1033	906	127	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	5713.4	5070.8	642.6	
55100500	STORM SEWER REMOVAL 12"	FOOT	824			824
60500040	REMOVING MANHOLES	EACH	17			17

REVISÉ 4/13/11 REVISÉ 4/20/11