

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				URBAN ST CLAIR 100% STATE ROADWAY 0005	RURAL ST CLAIR 100% STATE ROADWAY 0005	RURAL MADISON 100% STATE ROADWAY 0005
20200100	EARTH EXCAVATION	CU YD	1315	900	255	160
* 25000200	SEEDING, CLASS 2	ACRE	0.75		0.5	0.25
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68		45	23
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68		45	23
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68		45	23
* 25100105	MULCH, METHOD 1	ACRE	0.75		0.5	0.25
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75		50	25
28100107	STONE RIPRAP, CLASS A4	SQ YD	126	6	97	23
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	46		19	27
28200200	FILTER FABRIC	SQ YD	126	6	97	23
31101810	SUBBASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	2960	2960		
31200100	STABILIZED SUBBASE 4"	SQ YD	2960	2960		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	27	2	19	6
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	103	72	25
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	71.1	21.4	18.7	31.0
40600300	AGGREGATE (PRIME COAT)	TON	341	103	90	148
40600895	CONSTRUCTING TEST STRIP	EACH	2	1		1
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	49			49
40600990	TEMPORARY RAMP	SQ YD	168	120		48
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	9547	2873	2511	4163
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	105	95		10
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	2960	2960		
42001300	PROTECTIVE COAT	SQ YD	5296	3024	1539	733
44000100	PAVEMENT REMOVAL	SQ YD	2960	2960		
44000400	GUTTER REMOVAL	FOOT	12015	255	7277	4483
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	312	187	42	83
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	506	19	18	469
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	161	31		130
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1208	254	280	674
54215547	METAL END SECTIONS 12"	EACH	2		1	1
60100945	PIPE DRAINS 12"	FOOT	50		25	25
60403500	GRATES, TYPE B	EACH	3		2	1
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	73	6	51	16
60602800	CONCRETE GUTTER, TYPE B	FOOT	9817	162	6376	3279
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	6000	1375	2112.5	2512.5
* 63000005	STEEL PLATE BEAM GUARDRAIL, TYPE B	FOOT	900	450	50	400
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	237.5	125	12.5	100
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	61	21	16	24
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	3	2	3
67100100	MOBILIZATION	L SUM	1	0.35	0.3	0.35
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.25	0.25	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.25	0.25	0.5

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				URBAN ST CLAIR 100% STATE ROADWAY 0005	RURAL ST CLAIR 100% STATE ROADWAY 0005	RURAL MADISON 100% STATE ROADWAY 0005
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.25	0.25	0.5
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.25	0.25	0.5
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	240	180	30	30
70300100	SHORT TERM PAVEMENT MARKING	FOOT	16168	5139	4224	6805
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	561	561		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	115074	31670	33280	50124
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	155	155		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	118	118		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	98	98		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	40658	11937	11446	17275
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	436	436		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	113254	29850	33280	50124
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	118	118		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	98	98		
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	125	125		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1820	1820		
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	155	155		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	605	263	131	211
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	141	50	37	54
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	62	22	16	24
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	593	251	131	211
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4730	1427	1249	2054
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	112865	34033	29727	49105
X5041800	CONCRETE ANCHORS	EACH	4		2	2
X6320100	GUARDRAIL REMOVAL SPECIAL	FOOT	2686	800	896	990
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	1	1		
* LR631020	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1	1		

\*SPECIALTY ITEM

FILE NAME =	USER NAME = betaj	DESIGNED - ESW	REVISED - 3-22-11	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SiVProjects\409-0028-9H E. 4 Lebanon 3P\dgr1\CA00 3r	beta\081623-dht-502 Revised.dgn	DRAWN - PDB	REVISED -					314	(110, 111)RS-4	MADISON & ST CLAIR	58	3
PLOT SCALE = 40,0000' / IN.		CHECKED - BRM	REVISED -		SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
PLOT DATE = 3/24/2011		DATE - 11-11-10	REVISED -		CONTRACT NO. 76E29							