RESURFACING SCHEDULE

LOCATION STATION TO STATION	BITUMINOUS MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 (TON)	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT (SQ YD)	TEMPORARY RAMP (SQ YD)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 (TON)	AGGREGATE WEDGE SHOULDER, TYPE B (TON)	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (SQ YD)
STA 63+21 TO STA 63+36	0.04	0.2	2.4		26.7	5.0		60.0
STA 63+36 TO STA 63+41	0.02	0.1	0.7		26.7	1.7		20.0
STA 63+50 TO STA 63+55	0.02	0.1	0.7		26.7	1.7		20.0
STA 63+55 TO STA 63+75	0.06	0.2	3.4			6.7		80.0
STA 63+75 TO STA 64+02	0.08	0.4	5.3			10.6		126.0
STA 64+02 TO STA 64+12	0.02	0.1	1.8			3.6		43.3
STA 64+12 TO STA 64+70	0.14	0.7	9.7			19.5		232.0
STA 64+70 TO STA 70+50	1.58	7.5	105.6			211.1		2513.3
STA 70+50 TO STA 71+86	0.40	1.9	26.7			53.3		634.7
STA 71+86 TO STA 72+62	0.20	1.0	13.8			27.7		329.3
STA 72+62 TO STA 74+60	0.58	2.8	38.8			77.6		924.0
STA 74+60 TO STA 88+19	3.40	16.3	228.3			456.6		5436.0
STA 88+19 TO STA 88+24	0.02	0.1	0.7		26.7	1.7		20.0
STA 101+75.7 TO STA 102+00.7	0.00	0.0	0.6		13.3	6.4		13.3
STA 102+00.7 TO STA 107+55	0.96	4.6	62.1			124.2		1531.5
STA 107+55 TO STA 138+92	5.68	27.2	380.6			761.2	77	9062.4
STA 138+92 TO STA 146+78	1.64	7.9	110.0			220.1		2620.0
STA 146+78 TO STA 182+68	6.50	31.1	435.4			870.8	85	10367.1
SAFETY EDGE						9.3		
SHOULDER BUILDUP							92	
SIDEROADS	0.08	0.4				4.2		
SUBTOTAL URBAN ST CLAIR COUNTY	21.42	102.6	1426.6	0	120.1	2873.0	254	34032.9
STA 182+68 TO STA 288+29	18.58	89.2	1248.5			2497.0	172	29726.4
SAFETY EDGE						9.9		
SHOULDER BUILDUP							108	
SIDEROADS	0.06	0.4				4.4		
SUBTOTAL RURAL ST CLAIR COUNTY	18.64	89.6	1248.5	0	0	2511.3	280	29726.4
STA 288+29 TO STA 367+56.5	14.12	67.6	945.6			1891.1	151	22513.3
STA 367+56.5 TO STA 371+87.5	0.90	4.3	59.6			120.7	11	1436.7
STA 371+87.5 TO STA 372+07.5	0.04	0.2	0.6		16.7	6.5		66.7
STA 373+73.5 TO STA 373+93.5	0.04	0.2	0.6		16.7	6.5		66.7
STA 373+93.5 TO STA 377+07.5	0.66	3.1	43.3			87.9	8	1046.7
STA 377+07.5 TO STA 459+86.5	14.96	71.8	1003.9			2009.0	204	23917.1
STA 459+86.5 TO STA 460+06.5	0.04	0.2	0.5		14.4	5.7		57.8
SAFETY EDGE						21.4		
SHOULDER BUILDUP							300	
SIDEROADS	0.26	0.9		48.86		13.6		
SUBTOTAL MADISON COUNTY	31.02	148.3	2054.1	48.86	47.8	4162.4	674	49105.0
SUBTOTAL	71.08	340.5	4729.2	48.9	167.9	9546.7	1208	112864.3
PAY TOTAL	71.1	341	4730	49	168	9547	1208	112865

GUARDRAIL SCHEDULE

LOCATION STATION	SIDE	STONE DUMPED RIPRAP, CLASS A3 (TON)	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS (FOOT)	STEEL PLATE BEAM GUARDRAIL, TYPE B (FOOT)	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 2 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 BLR 23-3 (EACH)	GUARDRAIL MARKERS, TYPE A (EACH)	TERMINAL MARKER - DIRECT APPLIED (EACH)	GUARDRAIL REMOVAL SPECIAL (FOOT)
86+79	LT		162.5				2		4	2	274
117+25	RT		187.5	50	18.75		2		5	2	190.5
117+25	LT		75	50	18.75	1	2	1	8	3	111.5
133+17	RT		75	50	12.50		2		4	2	
133+17	LT		162.5	50	12.50		2		4	2	
149+80	RT		162.5	50	12.50		2		4	2	
149+80	LT		162.5	50	12.50		2		4	2	
162+18	LT		100	50	12.50	1	3		8	3	
179+65	RT		187.5	50	12.50		2		5	2	112
179+65	LT		100	50	12.50		2		4	2	112
SUBTOTAL URBAN ST CLAIR COUNTY		0	1375.0	450	125.00	2	21	1	50	22	800
210+99	RT		362.5				2		6	2	140
211+58	LT		362.5				2		6	2	137
252+31	RT	19	237.5				2		4	2	190
252+31	LT		250	50	12.50		2		5	2	111
273+54	RT		237.5				2		4	2	178
273+54	LT		212.5				2		4	2	
278+63	RT		237.5				2		4	2	140
278+91	LT		212.5				2		4	2	
SUBTOTAL RURAL ST CLAIR COUNTY		19	2112.5	50	12.50	0	16	0	37	16	896
303+75	LT		337.5				2		6	2	160
309+45	LT		150				2		4	2	140
316+80	RT	27	162.5	50	12.50		2		5	2	201
316+80	LT		250	50	12.50		2		4	2	113
364+72	RT		212.5				2		4	2	
385+30	LT		475				2		7	2	
403+88	RT		150	50	12.50		2		4	2	
403+88	LT		150	50	12.50		2		4	2	
415+18	RT		150	50	12.50		2		4	2	
415+18	LT		150	50	12.50		2		4	2	
446+28	RT		162.5	50	12.50		2		4	2	175
446+28	LT		162.5	50	12.50		2		4	2	201
SUBTOTAL MADISON COUNTY		27	2512.5	400	100.00	0	24	0	54	24	990
TOTAL		46	6000.0	900	237.50	2	61	1	141	62	2686
ROUNDED TOTAL		46	6000.0	900	237.50	2	61	1	141	62	2686

GUTTER SCHEDULE

LOCATION STATION	SIDE	STONE RIPRAP, CLASS A4 (SQ YD)	FILTER FABRIC (SQ YD)	AGGREGATE SURFACE COURSE, TYPE B•• (TON)	METAL END SECTIONS, 12" (EACH)	PIPE DRAINS 12" (FOOT)	GRATES, TYPE B (EACH)	PROTECTIVE COAT (SQ YD)	CLASS SI CONCRETE (OUTLET) (CU YD)	CONCRETE GUTTER, TYPE B (FOOT)	GUTTER REMOVAL (FOOT)	CONCRETE ANCHORS (EACH)
STA 163+47 TO STA 165+47	RT	5.6	5.6	2.3				64	5.5	162	255	
SUBTOTAL URBAN ST CLAIR COUNTY		5.6	5.6	2.3	0	0	0	64	6	162	255	0
STA 208+52 TO STA 210+39	LT				1	25	1	49	2.3	187	225	2
STA 214+94 TO STA 222+18	LT	16.7	16.7					158	2.9	724	799	
STA 214+99 TO STA 223+63	RT	17.2	17.2	2.4				194	5.6	824	940	
STA 225+86 TO STA 228+25	LT	5.6	5.6	2.1				71	5.3	203	285	
STA 242+86 TO STA 251+26	LT	12.3	12.3	1.9				197	6.6	808	912	
STA 242+86 TO STA 252+01	RT	7.2	7.2	3.4			1	213	8.0	857	987	
STA 254+16 TO STA 262+14	LT	5.6	5.6					172	2.9	798	848	
STA 254+16 TO STA 261+91	RT	5.6	5.6	6.0				189	9.7	673	825	
STA 281+39 TO STA 288+29	RT	15.0	15.0	2.4				156	2.2	650	750	
STA 281+77 TO STA 288+29	LT	11.7	11.7					140	5.0	652	706	
SUBTOTAL RURAL ST CLAIR COUNTY		96.9	96.9	18.2	1	25	2	1539	51	6376	7277	2
STA 288+29 TO STA 301+92	RT	11.7	11.7	2.8				287	5.2	1316	1417	
STA 288+29 TO STA 293+60	LT							107	0.6	531	531	
STA 298+85 TO STA 302+26	LT				1	25	1	79	2.3	341	775	2
STA 310+47 TO STA 313+46	LT			1.3				70	2.8	271	850	
STA 310+47 TO STA 319+01	RT	11.1	11.1	2.0				190	5.1	820	910	
SUBTOTAL MADISON COUNTY		22.8	22.8	6.1	1	25	1	733	16.0	3279	4483	2
TOTAL		125.3	125.3	26.6	2	50	3	2336	73	9817	12015	4
ROUNDED TOTAL		126	126	27	2	50	3	2336•	73	9817	12015	4

• NOT A TOTAL QUANTITY

•• AGGREGATE SURFACE COURSE, TYPE B INCLUDED FOR GUTTER ENTRANCES.

PCC PAVEMENT SCHEDULE

LOCATION STATION TO STATION	SUBBASE GRANULAR MATERIAL, TYPE B 12" (SQ YD)	STABILIZED SUBBASE 4" (SQ YD)	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED) (SQ YD)	PROTECTIVE COAT (SQ YD)	PAVEMENT REMOVAL (SQ YD)
STA 88+24 TO STA 95+64	2960	2960	2960	2960	2960
SUBTOTAL URBAN ST CLAIR COUNTY	2960	2960	2960	2960	2960
PAY TOTAL	2960	2960	2960	2960•	2960

• NOT A TOTAL QUANTITY

FILE NAME = S:\Projects\409-0028-9HY IL 4 Lebanon 3P\dgn\CADD Sheets\D876E29-sht-schedule.dgn	USER NAME = betsy	DESIGNED - ESW	REVISED - 3-22-11
		DRAWN - PDB	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED - BRM	REVISED -
	PLOT DATE = 3/24/2011	DATE - 11-11-10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. 1 OF 3 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
314	(110, 111)RS-4	MADISON & ST CLAIR	58	8
		CONTRACT NO. 76E29		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT