SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	0003 ROADWAY 80% FEDERAL 20% STATE	0021 TRAFFIC SIGNALS 80% FEDERAL 20% STATE
		CONSTRUCTION TYPE CODE			
55200600	STORM SEWERS JACKED IN PLACE, 18"	FOOT	80	80	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	35.4	35.4	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	18	18	
60107600	PIPE UNDERDRAINS 4"	FOOT	4832	4832	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	204	204	
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60500060	REMOVING INLETS	EACH	4	4	
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	429	429	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	287	287	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	249	249	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1214	1214	
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	340	340	
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	488	488	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	11457	11457	
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	550	550	
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	
67100100	MOBILIZATION	LSUM	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	48	48	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	32	32	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2715	2715	
70300210	TEMPORARY PAVEMENT MARKIING LETTERS AND SYMBOLS	SQ FT	739.8	739.8	
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	28049	28049	
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	1760	1760	
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	338	338	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14906	14906	
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	82.2	82.2	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15441	15441	
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	700	700	
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	86	86	
*78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	657.6	657.6	
*78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	20816	20816	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	0003 ROADWAY 80% FEDERAL 20% STATE	0021 TRAFFIC SIGNALS 80% FEDERAL 20% STATE
		CONSTRUCTION TYPE CODE			
*78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	1060	1060	
*78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	252	252	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100	100	
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	11	11	
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100	
*80300100	LOCATING UNDERGROUND CABLE	FOOT	40		40
*81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	633		633
*81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	664		664
*81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	55		55
*81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	20		20
*81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	177		177
*81021330	CONDUIT, PUSHED, 2" DIA., PVC	FOOT	81		81
*81021340	CONDUIT, PUSHED, 2 1/2" DIA., PVC	FOOT	150		150
*81021350	CONDUIT, PUSHED, 3" DIA., PVC	FOOT	113		113
*81021360	CONDUIT, PUSHED, 3 1/2" DIA., PVC	FOOT	140		140
*81021370	CONDUIT, PUSHED, 4" DIA., PVC	FOOT	238		238
*81400100	HANDHOLE	EACH	12		12
*81500100	GULFBOX JUNCTION	EACH	4		4
*81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP - TYPE USE) 3-1/C NO. 10	FOOT	1271		1271
*81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1549		1549
*82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	8		8
*82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240 VOLT, 60 AMP	EACH	1		1
*85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1
*86000100	MASTER CONTROLLER	EACH	1		1
*86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1		1
*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5 C	FOOT	2657		2657
*87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9 C	FOOT	1859		1859
*87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12 C	FOOT	801		801
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	12091		12091

*SPECIALTY ITEM