

SUMMARY OF QUANTITIES					
CODE NO.	ITEM	CONSTRUCTION TYPE CODE		0003	0021
		UNIT	TOTAL QUANTITIES	ROADWAY 80% FEDERAL 20% STATE	TRAFFIC SIGNALS 80% FEDERAL 20% STATE
*87502310	TRAFFIC SIGNAL POST, PAINTED STEEL 16 FT.	EACH	2		2
*87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	2		2
*87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	2		2
*87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6		6
*87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3		3
*87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	56		56
*88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2
*88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12		12
*88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2
*88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3 SECTION, BRACKET MOUNTED	EACH	2		2
*88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2		2
*88200100	TRAFFIC SIGNAL BACKPLATE	EACH	12		12
*88500100	INDUCTIVE LOOP DETECTOR	EACH	13		13
*88500200	INDUCTIVE LOOP DETECTOR WITH SYSTEM OUTPUT	EACH	8		8
*88600100	DETECTOR LOOP, TYPE I	FOOT	2785		2785
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1

* SPECIALTY ITEM