

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	JEFFERSON ROADWAY URBAN	JEFFERSON BRIDGE URBAN
				90% FED 10% STATE 0003	041-0012 (NB) 041-0013 (SB) 90% FED/10% ST 0014
CONSTRUCTION TYPE CODE					
XZ191203	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 3/4"	SQ YD	1,642		1642
* X0300780	ELECTRIC PIEZO SENSOR CABLE IN CONDUIT	FOOT	856	856	
* X0323014	ELECTRIC CABLE IN CONDUIT, CONOGA-30003	FOOT	1,572	1572	
* X0323015	PIEZO ELECTRIC AXLE SENSOR, CLASS II	FOOT	6	6	
X0323236	TEMPORARY INLET	EACH	14	14	
<del>X0325571</del>	<del>TRAFFIC CONTROL SUPERVISOR</del> <b>DELETED</b>	<del>CAL DA</del>	<del>64</del>	<del>64</del>	
X0326458	PAVEMENT REPLACEMENT, SPECIAL	SQ YD	10,586	10,586	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	7,917	7,659	258
X4404400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	10,586	10,586	
X5030530	FLOOR DRAIN EXTENSION	EACH	24		24
<del>X7010237</del>	<del>CHANGEABLE MESSAGE SIGN, SPECIAL</del> <b>DELETED</b>	<del>CAL DA</del>	<del>120</del>	<del>120</del>	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	83,882	83,882	
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	27,547	27,547	
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	7,207	7,207	
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	307	307	
* X8190205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	112	112	
* X8570000	SMART TRAFFIC MONITORING SYSTEM	L SUM	1	1	
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	16		16
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	37,600	37,600	
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1,642		1,642
Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	1,642		1,642
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	13		13
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	10	6	4
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1
Z0055605	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SQ YD	55,661	55,661	
Z0062456	TEMPORARY PAVEMENT	SQ YD	8,856	8,856	
20200100	EARTH EXCAVATION	CU YD	48,118	48,118	
20400100	BORROW EXCAVATION	CU YD	58,851	58,851	
20900110	POROUS GRANULAR BACKFILL	CU YD	104	104	
* 25C 00200	SEEDING, CLASS 2	ACRE	44	44	
* 25C 00350	SEEDING, CLASS 7	ACRE	44	44	

\*SPECIALTY ITEM

REVISSED 4/15/11

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\pwsdat\colemm\0169788\78172	sht_schedules.dgn	DRAWN -	REVISED -			57	.	Jefferson	422	5
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -							
	PLOT DATE = 2/25/2011	DATE -	REVISED -							
						SCALE:	SHEET NO.	OF	SHEETS	STA.
										TO STA.
						ILLINOIS FED. AID PROJECT				