

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	JEFFERSON ROADWAY URBAN	JEFFERSON BRIDGE URBAN
				90% FED 10% STATE	041-0012 (NB) 041-0013 (SB) 90% FED/10% ST
	CONSTRUCTION TYPE CODE			0003	0014
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7,900	7,900	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3,950	3,950	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3,950	3,950	
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	88	88	
* 25100115	MULCH, METHOD 2	ACRE	88	88	
* 25100630	EROSION CONTROL BLANKET	SQ YD	26,600	26,600	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	13,200	13,200	
28000305	TEMPORARY DITCH CHECKS	FOOT	1,210	1,210	
28000400	PERIMETER EROSION BARRIER	FOOT	11,850	11,850	
28000500	INLET AND PIPE PROTECTION	EACH	20	20	
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	166	166	
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	151,752	151,752	
30201500	LIME	TON	4,506.9	4,506.9	
X3120005	STABILIZED SUBBASE - HOT-MIX ASPHALT (VARIABLE DEPTH)	TON	17,933	17,933	
31200500	STABILIZED SUBBASE HOT-MIX ASPHALT, 4"	SQ YD	142,594	142,594	
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24	24	
40600990	TEMPORARY RAMP	SQ YD	478	478	
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	29	29	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,976	2,976	
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	3,304	3,304	
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	11,378	11,378	
42001200	PAVEMENT FABRIC	SQ YD	1,705	1,705	
42001300	PROTECTIVE COAT	SQ YD	14,682	14,682	
42100300	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	27,223	27,223	
42100310	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2"	SQ YD	72,869	72,869	
42100340	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	46,552	46,552	
42100615	PAVEMENT REINFORCEMENT	SQ YD	146,644	146,644	
42101300	PROTECTIVE COAT	SQ YD	146,448	146,448	
42101436	LUG SYSTEM COMPLETE 36'	EACH	8	8	
44000100	PAVEMENT REMOVAL	SQ YD	64,461	64,461	
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	94,169	94,169	
44004250	PAVED SHOULDER REMOVAL	SQ YD	52,153	48,949	3,204
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	208	208	
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	1,497	1,497	
44201299	DOWEL BARS 1 1/2"	EACH	1,064	1,064	
44213000	PATCHING REINFORCEMENT	SQ YD	10,586	10,586	
44213200	SAW CUTS	FOOT	28,267	28,267	

*SPECIALTY ITEM

▲ REVISED 4/12/11 ▲ REVISED 4/15/11

FILE NAME =	USER NAME = rollvr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et\pw\work\p\dot\rollvr\d0169788\78172	ght_schedules.dgn	DRAWN -	REVISED -			57	.	Jefferson	422	6
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -		SCALE:					
	PLOT DATE = 2/23/2011	DATE -	REVISED -		SHEET NO. OF SHEETS STA. TO STA.					CONTRACT NO. 78172
ILLINOIS FED. AID PROJECT										