

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	JEFFERSON ROADWAY URBAN	JEFFERSON BRIDGE URBAN
				90% FED 10% STATE	041-0012 (NB) 041-0013 (SB) 90% FED/10% ST
CONSTRUCTION TYPE CODE				0003	0014
60500060	REMOVING INLETS	EACH	6	6	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	8,223	8,223	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	9	9	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	26	26	
63200310	GUARDRAIL REMOVAL	FOOT	5,632	5,459	173
63300900	VERTICAL ADJUSTMENT OF GUARDRAIL	FOOT	516	516	
63500105	DELINEATORS	EACH	267	267	
64200105	SHOULDER RUMBLE STRIPS	FOOT	68,630	68,630	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	31	31	
67100100	MOBILIZATION	L SUM	1	1	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	8		8
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	4		4
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	8	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1	
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	250	250	
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	9,600	9,600	
* 81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	13,788	13,788	
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	33	33	
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	43	43	
* 83010600	LIGHT POLE, ALUMINUM, 50FT. M.H., 15FT. MAST ARM	EACH	43	43	
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	608	608	
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	76	76	
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	341,581	315,476	26,105
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	113,860	113,860	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	21,737.5	21,737.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	42,325	40,325	2,000
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID- LINE 4"	FOOT	83,873	83,873	
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -INLAID- LINE 6"	FOOT	25,043	25,043	
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -INLAID- LINE 8"	FOOT	7,194	7,194	
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -INLAID- LINE 12"	FOOT	281	281	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	760	760	
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	844	844	
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	102	102	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	25	25	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	27,793	26,343	1,450
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	434	434	
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	100	100	
81012400	CONDUIT IN TRENCH, 1 1/4" PVC	FOOT	112	112	
81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	112	112	
81400200	HEAVY-DUTY HANDHOLE	EACH	4	4	
* 81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	210	210	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	13,530	13,530	
* 86300300	CONTROLLER CABINET TYPE III	EACH	1	1	
* 87800215	CONCRETE FOUNDATION, TYPE D	EACH	1	1	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	528	528	

2

\*SPECIALTY ITEM

2 REVISED 4/15/11

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\pwidot\colemm\0169788\78172	sht_schedules.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	Jefferson	422	8
	PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -								CONTRACT NO.	78172	
	PLOT DATE = 2/25/2011	DATE -	REVISED -								ILLINOIS FED. AID PROJECT		