

ITEM NUMBER	S.P.	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	80% STATE / 20% CITY			100% CITY NON-PARTICIPATING
						ROADWAY	BRIDGE	TRAINEES	
						0003	0010	0042	
121		60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	7,702	7,702			
122		60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	277	277			
123	*	60624610	CORRUGATED MEDIAN (DOWELLED)	SO FT	1,657	1,657			
124		63200310	GUARDRAIL REMOVAL	FOOT	9	9			
125		66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	7	7			
△ 126	*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	5,050	3,600	1,450		
△ 127		66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1			
△ 128		66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4			
129		67100100	MOBILIZATION	L SUM	1	1			
130		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,390	2,390			
131		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	796	796			
132		72000100	SIGN PANEL - TYPE 1	SO FT	408	408			
133		72000200	SIGN PANEL - TYPE 2	SO FT	138	138			
134		72000300	SIGN PANEL - TYPE 3	SO FT	60	60			
135		72400310	REMOVE SIGN PANEL - TYPE 1	SO FT	180	180			
136		72400320	REMOVE SIGN PANEL - TYPE 2	SO FT	15	15			
137		72400330	REMOVE SIGN PANEL - TYPE 3	SO FT	96	96			
138		72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	304	304			
△ 139		78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	758	758			
△ 140		78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	10,300	10,300			
△ 141		78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	132	132			
△ 142		78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	146	146			
△ 143		78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	644	644			
△ 144		78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	267	267			
△ 145		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	78	78			
146		78300100	PAVEMENT MARKING REMOVAL	SO FT	530	530			
△ 147		80400100	ELECTRIC SERVICE INSTALLATION	EACH	2	2			
△ 148		81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	140	140			
△ 149		81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	840	840			
△ 150		81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	8,503	8,503			


ITEM NUMBER	S.P.	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	80% STATE / 20% CITY			100% CITY NON-PARTICIPATING
						ROADWAY	BRIDGE	TRAINEES	
						0003	0010	0042	
△ 151		81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	1,985	1,985			
△ 152		81301370	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 18" X 12" X 8"	EACH	5	5			
△ 153		81400100	HANDHOLE	EACH	14	14			
△ 154		81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	8,225	8,225			
△ 155		81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	16,620	16,620			
△ 156		81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	510	510			
△ 157	*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6,163	6,163			
△ 158		82103600	LUMINAIRE, SODIUM VAPOR, VERTICAL MOUNT, 250 WATT	EACH	9	9			
△ 159		82103700	LUMINAIRE, SODIUM VAPOR, VERTICAL MOUNT, 400 WATT	EACH	42	42			
△ 160		82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100 AMP	EACH	2	2			
△ 161		83006200	LIGHT POLE, ALUMINUM, 30 FT. M.H., 6 FT. MAST ARM	EACH	9	9			
△ 162		83008200	LIGHT POLE, ALUMINUM, 40 FT. M.H., 6 FT. MAST ARM	EACH	42	42			
△ 163		83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	559	559			
△ 164		83800505	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT	EACH	43	43			
△ 165		89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	7	7			
△ 166		89502380	REMOVE EXISTING HANDHOLE	EACH	2	2			
△ 167		A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4			
△ 168		A2006816	TREE, QUERCUS MUEHLENBERGII (CHINKAPIN OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4			
△ 169		A2007916	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4			
△ 170		A2008468	TREE, ULMUS AMERICANA PRINCETON (PRINCETON AMERICAN ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4			
△ 171		A2008722	TREE, ULMUS PATRIOT (PATRIOT ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4			
172	*	X0321865	ANTI-GRAFFITI PROTECTION SYSTEM	SO FT	10,921				10,921
173	*	X0322924	RETAINING WALL REMOVAL	SO FT	450	450			
174	*	X0322936	REMOVE EXISTING FLARED END SECTION	EACH	1	1			
△ 175	*	X0323172	DUCTILE IRON WATER MAIN BEND, 45 DEGREES, 8 INCHES	EACH	29				29
△ 176	*	X0323182	DUCTILE IRON WATER MAIN REDUCER, 8"X6"	EACH	3				3
△ 177	*	X0323760	SANITARY SEWER SERVICE, 6" PVC, COMPLETE	EACH	1				1
△ 178	*	X0323820	DUCTILE IRON WATER MAIN TEE, 8" X 8"	EACH	11				11
△ 179	*	X0323821	DUCTILE IRON WATER MAIN REDUCER, 10"X8"	EACH	3				3
△ 180	*	X0324445	DUCTILE IRON WATER MAIN FITTINGS 8" 22.5 DEGREE BEND	EACH	5				5

NOTES:

- INDICATES SPECIAL PROVISION
- INDICATES IDOT RECURRING SPECIAL PROVISION
- BDE INDICATES IDOT BDE SPECIAL PROVISION
- GBSP INDICATES IDOT GBSP SPECIAL PROVISION

△ SPECIALTY ITEMS

L:\PROJECTS\9902\9902\00-00-00\CAADD_Sheets\15_500_03.dgn



USER NAME - Steve Frango	DESIGNED - SJP / MNB	REVISED -
	DRAWN - ERD	REVISED -
PLOT SCALE = 40.0000 1" = 10'	CHECKED - SJP	REVISED -
PLOT DATE = 02-04-11	DATE - 02/04/2011	REVISED -

CITY OF ROCKFORD
MORGAN STREET BRIDGE

SUMMARY OF QUANTITIES			
SCALE: N/A	SHEET NO. 3 OF 4 SHEETS	STA.	TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5077	99-00493-00-BR	WINNEBAGO	253	9
FED. ROAD DIST. NO. 2 [ILLINOIS] FED. AID PROJECT BRM-5099651			CONTRACT NO. 85529	