

ITEM NUMBER	S.P.	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	80% STATE / 20% CITY			100% CITY
						ROADWAY 0003	BRIDGE 0010	TRAINEES 0042	
△ 181	*	X0324449	DUCTILE IRON WATER MAIN FITTINGS, MECHANICAL JOINT 8"x6" HYDRANT TEE	EACH	10				10
182	*	X0324554	CONCRETE FLAT SLAB TOP	EACH	1	1			
△ 183	*	X0324741	HDP PIPE 8"	FOOT	100				100
△ 184	*	XY00823	CONDUIT INSTALLED, 1 1/2" PVC	FOOT	182	182			
△ 185	*	X0325340	FIRE HYDRANT WITH 6" VALVE AND VALVE BOX	EACH	10				10
186	GBSP	X0326414	HIGH LOAD MULTI-ROTATIONAL BEARINGS, FIXED - 2750K	EACH	2		2		
187	*	X0326414	STAMPED COLORED PORTLAND CEMENT CONCRETE MEDIAN SURFACE 8 INCH	SO FT	2,626	2,626			
188	*	X0326891	TEMPORARY ACCESS ROAD (SPECIAL)	SO YD	2,222				2,222
189	GBSP	X0327139	AGGREGATE COLUMN GROUND IMPROVEMENT	L SUM	1		1		
△ 190	*	X0839900	SANITARY SEWER REMOVAL 6"	FOOT	100				100
△ 191	*	X0840000	SANITARY SEWER REMOVAL 8"	FOOT	1,098				1,098
192	*	X2010510	CLEARING AND GRUBBING	LSUM	1	1			
193	*	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	7,243	7,090	153		
194	*	X2800500	INLET PROTECTION, SPECIAL	EACH	70	70			
195	*	X4403800	MEDIAN SURFACE REMOVAL	SO FT	2,847	2,847			
196	*	X5011100	FOUNDATION REMOVAL	EACH	1	1			
△ 197	*	X5091725	BICYCLE RAILING, SPECIAL	FOOT	1,253		1,253		
△ 198	*	X5091755	PARAPET RAILING, SPECIAL	FOOT	1,281		1,281		
199	*	X5150110	NAME PLATES (SPECIAL)	EACH	4				4
200	GBSP	X510280	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION - 2800K	EACH	2		2		
201	*	X5539700	STORM SEWERS TO BE CLEANED	FOOT	90	90			
△ 202	*	X5630004	CUT AND CAP EXISTING 4" WATER MAIN	EACH	6				6
△ 203	*	X5630006	CUT AND CAP EXISTING 6" WATER MAIN	EACH	11				11
△ 204	*	X5630008	CUT AND CAP EXISTING 8" WATER MAIN	EACH	2				2
△ 205	*	X5630010	CUT AND CAP EXISTING 10" WATER MAIN	EACH	6				6
△ 206	*	X5630704	CONNECTION TO EXISTING WATER MAIN 4"	EACH	4				4
△ 207	*	X5630706	CONNECTION TO EXISTING WATER MAIN 6"	EACH	4				4
△ 208	*	X5630708	CONNECTION TO EXISTING WATER MAIN 8"	EACH	4				4
△ 209	*	X5630710	CONNECTION TO EXISTING WATER MAIN 10"	EACH	6				6
210	*	X6024242	INLETS, SPECIAL, NO. 1	EACH	18	18			


ITEM NUMBER	S.P.	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	80% STATE / 20% CITY			100% CITY
						ROADWAY 0003	BRIDGE 0010	TRAINEES 0042	
211	*	X6024244	INLETS, SPECIAL, NO. 2	EACH	32	32			
△ 212	*	XX00952	MODIFIED JUNCTION CHAMBER	EACH	1				1
△ 213	*	X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	11				11
△ 214	*	X6026051	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	5				5
△ 215	*	X6026054	SANITARY MANHOLES TO BE REMOVED	EACH	12				12
216	*	X6026622	VALVE VAULTS TO BE REMOVED	EACH	20	20			
217	*	X6026632	VALVE BOXES TO BE REMOVED	EACH	18	18			
218	*	X6062700	CONCRETE GUTTER, TYPE A (SPECIAL)	FOOT	954	954			
219	*	X6640300	CHAIN LINK FENCE REMOVAL	FOOT	98	98			
220	*	X6660445	RIGHT-OF-WAY AND PROPERTY CORNERS	EACH	17	17			
221	*	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	32	32			
222	*	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1	1			
△ 223	*	XX003525	DUCTILE IRON WATER MAIN FITTING - 8" X 4" REDUCER	EACH	3				3
△ 224	*	XX005003	DUCTILE IRON WATER MAIN FITTING - 10" X 6" TEE	EACH	3				3
225	*	XX005488	STEEL CASING BORED AND JACKED 48"	FOOT	60	60			
△ 226	*	XX005786	DUCTILE IRON WATER MAIN FITTINGS TEE 8" X 4"	EACH	1				1
△ 227	*	XX005787	DUCTILE IRON WATER MAIN FITTINGS TEE 8"x6"	EACH	2				2
△ 228	*	XX006241	GATE VALVE AND BOX 8"	EACH	19				19
△ 229	*	XX006243	WATER SERVICE INSTALL, 1" COMPLETE	EACH	25				25
△ 230	*	XX006244	WATER SERVICE INSTALL, 2" COMPLETE	EACH	4				4
231	*	XX006652	STAMPED COLORED PORTLAND CEMENT CONCRETE MEDIAN SURFACE 4 INCH (SPECIAL)	SO FT	2,893	2,893			
△ 232	*	XX007263	GATE VALVE WITH BOX 4"	EACH	1				1
△ 233	*	XX007758	ADJUSTING WATER VALVE BOXES	EACH	2				2
△ 234	*	XX008156	LINE STOPS 10"	EACH	2				2
235	*	XX008455	INLET BOX, SPECIAL	EACH	3	3			
236	**	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
237		Z0018004	DRAINAGE SCUPPERS, DS-12	EACH	12		12		
238	GBSP	Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SO FT	5,163		5,163		
239	GBSP	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	80		80		
240	BDE	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	2	2			
241	*	Z0051398	REMOVE EXISTING SIGN POST	EACH	27	27			
242	*	XX008524	STEEL FABRICATED PARAPET WALL INSERT	EACH	1				1
243	*	Z0062456	TEMPORARY PAVEMENT	SO YD	40	40			
244	BDE	Z0076600	TRAINEES	HOUR	1,000				1,000
△ 245	*	Z0077002	WATER MAIN REMOVAL	FOOT	200				200

NOTES:

- INDICATES SPECIAL PROVISION
- INDICATES IDOT RECURRING SPECIAL PROVISION
- BDE INDICATES IDOT BDE SPECIAL PROVISION
- GBSP INDICATES IDOT GBSP SPECIAL PROVISION

△ SPECIALTY ITEMS

I:\cmt\cmt\020602\020602.dwg sheets 18, 500, 04.dwg



USER NAME = Steve Frange	DESIGNED - SJP / MNB	REVISED -
	DRAWN - ERD	REVISED -
PLOT SCALE = 40,0000 1" = 40'	CHECKED - SJP	REVISED -
PLOT DATE = 02/04/11	DATE - 02/04/2011	REVISED -

CITY OF ROCKFORD
MORGAN STREET BRIDGE

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A. RTE. 5077	SECTION 99-00493-00-BR	COUNTY WINNEBAGO	TOTAL SHEETS 253	SHEET NO. 10
FED. ROAD DIST. NO. 2 ILLINOIS			CONTRACT NO. 85529	
FED. AID PROJECT BRN-50991651				