



- NOTES:
1. ALL PAVEMENT MARKINGS SHALL BE EPOXY UNLESS OTHERWISE NOTED.
 2. PAVEMENT MARKING, INCLUDING LETTERS AND SYMBOLS, SHALL BE PLACED IN ACCORDANCE WITH IDOT DISTRICT 2 STD. 41.1.
 3. RAISED REFLECTIVE PAVEMENT MARKERS SHOULD BE PLACED IN ACCORDANCE WITH STD. 741001-03.
 4. ALL SIGNS SHOULD BE PLACED BASED ON 2009 MUTCD AND SIZED FOR A MULTI-LANE CONVENTIONAL ROAD.

MATCHLINE STA. 40+00.00

MATCHLINE STA. 46+00.00

- PROPOSED SIGNS GROUND MOUNTED STA. 40+02
- R15-1 24"x4.5"
 - R15-2P 13.5"x9"
 - R1-1 18"x18"
 - R15-8 18"x9"

L:\ROCKFORD\9826802\0-m\1000_Sheets\A.Pk. 28.02.dgn



USER NAME = Steve Prange	DESIGNED - SJP / MNB	REVISED -
PLOT SCALE = 40,0000' / IN.	DRAWN - ERD	REVISED -
PLOT DATE = 02/04/11	CHECKED - SJP	REVISED -
	DATE - 02/04/2011	REVISED -

**CITY OF ROCKFORD
MORGAN STREET BRIDGE**

PAVEMENT MARKING, LANDSCAPING, AND SIGNING PLAN

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5077	99-00493-00-BR	WINNEBAGO	253	93
CONTRACT NO. 85529			FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT BRM-509965	