



BILL OF MATERIAL

Item	Unit	Total
Permanent Steel Sheet Piling	Sq. Ft.	5,243

NOTES

* Abutment cap details not shown for clarity. See Structural Sheet 12 of 17 for details.

** After sheeting is driven the Contractor shall cut a notch in the sheeting as shown, then form & pour the reinforced concrete abutment cap, then lastly place a 3/8" thick plate in the gap for tight fit and weld. See Detail "B". Cost for this work shall be included in the contract unit price per Square Foot for Permanent Steel Sheet Piling.

The Contractor shall be paid for furnished sheeting as shown and Contractor shall drive the sheeting an extra 6" if top is not damaged, as directed by the Engineer.

USER NAME =	DESIGNED - M. C. WAGNER	REVISED -
PLOT SCALE =	CHECKED - B. K. CONVERSE	REVISED -
PLOT DATE =	DRAWN - F. D. LACHAT	REVISED -
	CHECKED - M. A. CACKLEY	REVISED -

BUREAU COUNTY
F.A.S. 184 (C.H. 11) OVER BIG BUREAU CREEK
STATION 59 + 75

NORTH ABUTMENT SHEET PILE LAYOUT
STRUCTURE NO. 006-3032
 STRUCTURAL SHEET NO. 13 OF 17 SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS	NO.
184	08-00211-00-BR	BUREAU	31	22
WHA* 1051D10		CONTRACT NO. 87462		
ILLINOIS FED. AID PROJECT BRS-0184(107)				

FILE NAME = S:\PROJECTS\2010\1051D10\BUREAU.CH11\DESIGN\STRUCT\Drawings\1051D10\AbutSheetP1e1a.dgn