

ROUTE NO	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 1857 C.H. 6	08-00074 -00-RS	MONROE	8	2

FEDERAL AID PROJECT
CONTRACT 97462

- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007 AND THE LATEST SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- THE THICKNESS OF THE HMA MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS, DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE.
- THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING MONROE COUNTY (48) HOURS IN ADVANCE PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES OR WORK REQUIRING INSPECTION OR APPROVAL.
- SEEDING IS NOT ANTICIPATED - THE DISTURBANCE OF SOIL AS DETERMINED BY THE ENGINEER AND SUBSEQUENT SEEDING SHALL BE THE RESPONSIBILITY OF AND THE COST TO THE CONTRACTOR. SEEDING WILL CONFORM TO SEC. 250 AND SEC. 251 OF THE STANDARD SPECIFICATIONS AND MEET THE SATISFACTION OF THE ENGINEER.
- NO OVERNIGHT LANE CLOSURES SHALL BE ALLOWED.
- TRAFFIC CONTROL SIGNS SHALL BE 48" FLOURESCENT ORANGE UNLESS OTHERWISE NOTED.
- ALL TEMPORARY PAVEMENT MARKINGS WILL BE PLACED IN SUCH A MANNER SO AS NOT TO INTERFERE WITH THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
- ACCESS SHALL BE PROVIDED FROM PRIVATE ENTRANCES AT ALL LOCATIONS DURING ALL STAGES.
- APRONS OF DRIVES AND MAILBOX TURNOUTS PAVED WITH EXTENDABLE SCREED WIDENERS WILL BE CONSIDERED AN INTEGRAL PART OF MAINLINE PAVING AND WILL NOT BE MEASURED FOR PAYMENT AS INCIDENTAL HOT-MIX ASPHALT SURFACING.
- AREA REFLECTIVE CRACK CONTROL SHALL BE PLACED BETWEEN THE LEVEL BINDER AND SURFACE COURSE, AT LOCATIONS NOTED ON SECTIONS.
- ALL EXCAVATION ADJACENT TO THE EDGE OF PAVEMENT SHALL BE PROTECTED BY TYPE 1 OR 2 BARRICADES WITH STEADY BURN LIGHTS.

FACTORS USED FOR QUANTITY CALCULATIONS ARE AS FOLLOWS:
 ALL HOT-MIX ASPHALT - 112 LB/SQ YD PER 1" THICKNESS
 AGGREGATE (PRIME COAT) - 5 LB/SQ YD
 BITUMINOUS MATERIAL (PRIME COAT) OVER ASPHALT - 0.05 GAL/SQ YD
 ALL AGGREGATE - 2.05 TONS/CU YD

- FLASHING BEACONS - REFER TO SPECIAL PROVISIONS AND DETAIL SHEET 8.
- PAVEMENT MARKINGS SHALL MATCH EXISTING - EXCEPT AS SHOWN IN THE SCHEDULE SHEET 4.

COMMITMENTS: NONE

SALVAGE: AGGREGATE MATERIAL EXCAVATED FOR HMA SHOULDER, REFER TO SPECIAL PROVISIONS.

SUMMARY OF QUANTITY

CODE	ITEM	UNIT	TOTAL QUANT.	STR QUANT.	HRRR QUANT.
20200100	EARTH EXCAVATION	CU. YD.	450.0	450.0	--
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	200	200	--
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	14580	14580	--
40600300	AGGREGATE (PRIME COAT)	TON	725	725	--
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	8100	8100	--
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0	--
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	980	980	--
40600990	TEMPORARY RAMP	SQ.YD.	135	135	--
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	14810	14810	--
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	132.5	132.5	--
44000157	HOT MIX ASPHALT SURFACE REMOVAL, 2"	SQ.YD.	3005	3005	--
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ.YD.	37,250	37,250	--
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5475	5475	--
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1365	--	1365
63200310	GUARDRAIL REMOVAL	FOOT	87.5	87.5	--
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL) TANGENT	EACH	2.0	2.0	--
* 63000001	STEEL PLATE BEAM GUARDRAIL TYPE A 6 FOOT POSTS	FOOT	87.5	87.5	--
64200105	SHOULDER RUMBLE STRIP	FOOT	12,000	--	12,000
67100100	MOBILIZATION	L SUM	1.0	1.0	--
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14,810	14,810	--
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	223,912	223,912	--
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	2220	2220	--
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	SQ.FT.	223,912	223,912	--
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	967	877	90
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	34.0	34.0	--
* X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	4.0	--	4.0
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1.0	1.0	--

* SPECIALTY ITEMS

BLUFF ROAD RESURFACING
 GENERAL NOTES &
 SUMMARY OF QUANTITIES
 SEC 08-00074-00-RS
 C.H. 6 - FAS 1857
 MONROE COUNTY, ILLINOIS