

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	(46-15847)WRS-2	LAKE	234	4
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 60956				

CODE NO.	PAY ITEM	UNIT	TOTAL	FUNDING BREAKDOWN									
				100% STATE	100% GRAYSLAKE FPD	100% LAKE COUNTY	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE
SUMMARY OF QUANTITIES				URBAN	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	SYSTEM INTERCONNECT	EMERGENCY PREEMPTION	EMERGENCY PREEMPTION	LAKE COUNTY
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y031-3D	J000-2A
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	3,144	3,144									
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	4,529	4,529									
35501323	HOT-MIX ASPHALT BASE COURSE, 9 3/4"	SO YD	2,151	2,151									
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,638	3,638									
40600300	AGGREGATE (PRIME COAT)	TON	30	30									
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	661	661									
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	11	11									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	44	44									
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	4,187	4,187									
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	884	884									
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	518	518									
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	352	352									
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	151	151									
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SO YD	66,382	66,382									
42001300	PROTECTIVE COAT	SO YD	17,271	17,271									
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	105	105									
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	2,282	2,282									
42400800	DETECTABLE WARNINGS	SO FT	60	60									
44000100	PAVEMENT REMOVAL	SO YD	58,027	58,027									
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	12,229	12,229									
44000300	CURB REMOVAL	FOOT	1,400	1,400									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	8,326	8,326									
44000600	SIDEWALK REMOVAL	SO FT	913	913									
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	3,244	3,244									
44004250	PAVED SHOULDER REMOVAL	SO YD	4,009	4,009									
44200116	PAVEMENT PATCHING, TYPE I, 10 INCH	SO YD	12	12									
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SO YD	1,512	1,512									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,874	1,874									
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SO YD	750	750									
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	154	154									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	791	791									
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2									
542A5497	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	14	14									
542D0220	PIPE CULVERTS, CLASS D, TYPE I 15"	FOOT	48	48									
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	6	6									
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2									

● INDICATES SPECIALTY ITEMS
 * NON-PARTICIPATING ITEMS

REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 U.S. ROUTE 45
 ILLINOIS ROUTE 120 TO WASHINGTON STREET

SCALE : NONE
 DATE: 12/14/09
 DRAWN BY: MLB
 CHECKED BY: MJL



12/14/09 - g:\401\2000\0005302\road\seq.sht

REV

Rev.