

ITEM NO.	ITEMS	UNIT	URBAN QUANTITY	TRAFFIC SIGNALS												SIDEWALK		WATER MAIN	COSTCO	
				ROADWAY	LIGHTING	LANDSCAPING	IL RTE 56 & TRANS AM	22nd ST & IL ROUTE 56	22nd ST & MIDWEST RD	22nd ST & OAKBROOK PLAZA	22nd ST & MACARTHUR DRIVE	22nd ST & PARKVIEW DR	22nd ST & IL RTE 83	INTER-CONNECT	EMERGENCY VEHICLE PREEMPTION	80% FED 10% STATE 10% OAK BROOK	80% FED 10% STATE 10% OAKBRK TERR	100% OAK BROOK	100% OAK BROOK	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% STATE 10% DUPAGE COUNTY	100% OAK BROOK	100% OAK BROOK	100% OAK BROOK	100% OAK BROOK	80% FED 20% STATE	100% OAK BROOK	80% FED 10% STATE 10% OAK BROOK	80% FED 10% STATE 10% OAKBRK TERR	100% OAK BROOK	100% OAK BROOK	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	640	J000-2A	Y030-1E	Y003	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	SFTY-1B	SFTY-1B	Y060	J000-2A	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	425	425																
20101000	TEMPORARY FENCE	FOOT	10,231	10,231																
20101200	TREE ROOT PRUNING	EACH	67	67																
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	44	44																
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	23	23																
20101700	SUPPLEMENTAL WATERING	UNIT	2	2																
20200100	EARTH EXCAVATION	CU YD	28,676	28,228																448
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12,011	11,611																400
20400800	FURNISHED EXCAVATION	CU YD	3,196	1,987																1,209
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3,919	3,919																
20800150	TRENCH BACKFILL	CU YD	11,711	11,003														678	30	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	390	390																
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	31,718	31,718																
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	6,280	6,280																
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	200	200																
* 25000210	SEEDING, CLASS 2A	ACRE	1.50	1.50																
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	540	540																
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	540	540																
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	540	540																
* 25100630	EROSION CONTROL BLANKET	SQ YD	6,280	6,280																
* 25200110	SODDING, SALT TOLERANT	SQ YD	31,718	31,718																
* 25200200	SUPPLEMENTAL WATERING	UNIT	1,710	1,710																
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,338	1,338																
28000305	TEMPORARY DITCH CHECKS	FOOT	912	912																
28000500	INLET AND PIPE PROTECTION	EACH	58	58																
28000510	INLET FILTERS	EACH	187	187																
28001000	AGGREGATE (EROSION CONTROL)	TON	75	75																
28200200	FILTER FABRIC	SQ YD	218	218																
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	5,324	5,324																
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	708	708																
40600300	AGGREGATE (PRIME COAT)	TON	15	15																
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	25	25																
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,297	1,297																
40701851	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/2"	SQ YD	789	618																171
42000316	PORTLAND CEMENT CONCRETE PAVEMENT 8 3/4" (JOINTED)	SQ YD	70,536	68,792																1,744
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	5,248	5,248																
42001300	PROTECTIVE COAT	SQ YD	52,438	52,438																
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	3,646	3,431																215
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	48,584													24,603	23,981			
42400800	DETECTABLE WARNINGS	SQ FT	1,010													300	710			
44000100	PAVEMENT REMOVAL	SQ YD	86,476	86,476																
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	10,505	10,505																

* SPECIALTY ITEM ** Y030-1E 100% OAK BROOK
NP NON-PARTICIPATING ITEM % Y080

FILE NAME = g:\CH07\0061\Road\SHETS\016012-SHT-S0.dgn	USER NAME = jmgolambo	DESIGNED - JMG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE. 1453	SECTION 55WRS	COUNTY	TOTAL SHEETS 362	SHEET NO. 3
PLOT SCALE = 50.0000' / IN.	DRAWN - BAW	CHECKED - JRH	REVISED -			CONTRACT NO. 60D12				
PLOT DATE = 4/2/2010	DATE - 4/1/2010	REVISED -	FED. ROAD DIST. NO. 7 (ILLINOIS) FED. AID PROJECT							
SHEET NO. 3 OF 362 SHEETS										