

ITEM NO.	ITEMS	UNIT	URBAN QUANTITY	TRAFFIC SIGNALS												SIDEWALK		WATER MAIN		COSTCO	
				ROADWAY	LIGHTING	LANDSCAPING	IL RTE 56 & TRANS AM	22nd ST & IL ROUTE 56	22nd ST & MIDWEST RD	22nd ST & OAKBROOK PLAZA	22nd ST & MACARTHUR DRIVE	22nd ST & PARKVIEW DR	22nd ST & IL RTE 83	INTER-CONNECT	EMERGENCY VEHICLE PREEMPTION	80% FED 10% STATE 10% OAK BROOK	80% FED 10% STATE 10% OAKBRK TERR	100% OAK BROOK	100% OAK BROOK		
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% STATE 10% DUPAGE COUNTY	100% OAK BROOK	100% OAK BROOK	100% OAK BROOK	100% OAK BROOK	80% FED 20% STATE	100% OAK BROOK						
55100700	STORM SEWER REMOVAL 15"	FOOT	1,169	J000-2A 1,169	Y030-1E	Y003	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	SFTY-1B	SFTY-1B	Y060	J000-2A		
55100900	STORM SEWER REMOVAL 18"	FOOT	855	855																	
55101100	STORM SEWER REMOVAL 21"	FOOT	80	80																	
55101200	STORM SEWER REMOVAL 24"	FOOT	1,625	1,625																	
55101400	STORM SEWER REMOVAL 30"	FOOT	174	174																	
55101600	STORM SEWER REMOVAL 36"	FOOT	267	267																	
56100500	WATER MAIN 4"	FOOT	21															21			
56100600	WATER MAIN 6"	FOOT	232															232			
56100700	WATER MAIN 8"	FOOT	20															20			
56100800	WATER MAIN 10"	FOOT	1,179															1,179			
56100900	WATER MAIN 12"	FOOT	1,366															1,366			
56104800	WATER VALVES 4"	EACH	1															1			
56104900	WATER VALVES 6"	EACH	1															1			
56105000	WATER VALVES 8"	EACH	1															1			
56105100	WATER VALVES 10"	EACH	8															8			
56105200	WATER VALVES 12"	EACH	3															3			
56106100	ADJUSTING WATER MAIN 3"	FOOT	60															60			
56106300	ADJUSTING WATER MAIN 6"	FOOT	40															40			
56106500	ADJUSTING WATER MAIN 10"	FOOT	50															50			
56106600	ADJUSTING WATER MAIN 12"	FOOT	235															235			
56200700	WATER SERVICE LINE 2"	FOOT	10															10			
56201800	CORPORATION STOPS 2"	EACH	2															2			
56300300	ADJUSTING WATER SERVICE LINES	FOOT	75															75			
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	4															4			
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	11															11			
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	16															16			
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2															2			
56500800	DOMESTIC WATER SERVICE BOXES	EACH	2															2			
60107600	PIPE UNDERDRAINS 4"	FOOT	3,470	3,470																	
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	14	14																	
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	39	39																	
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	4	4																	
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	52	50															2		
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	2	1															1		
60204825	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	2	2																	
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	7	7																	
60205310	CATCH BASINS, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2																	
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	26	26																	
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	22	16															6		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	19	18															1		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	45	45																	
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3																	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	9	9																	
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	20	20																	

\* SPECIALTY ITEM      \*\* Y030-1E 100% OAK BROOK  
 NP NON-PARTICIPATING ITEM      /% Y080

FILE NAME = gr\CH07\0061\Road\SHEETS\0160012-SHT-SID.dgn	USER NAME = jmgolomba	DESIGNED - JMG	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A. RTE. 1453	SECTION 55WRS	COUNTY	TOTAL SHEETS 362	SHEET NO. 5
PLOT SCALE = 50.0000' / IN.	CHECKED - JRH	REVISED -	SHEET NO. 5 OF 362 SHEETS			CONTRACT NO. 60D12				
PLOT DATE = 4/2/2010	DATE - 4/1/2010	REVISED -	FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT							