

ITEM NO.	ITEMS	UNIT	URBAN QUANTITY	TRAFFIC SIGNALS																	SIDEWALK		WATER MAIN		COSTCO	
				ROADWAY	LIGHTING	LANDSCAPING	IL RTE 56 & TRANS AM	22nd ST & IL ROUTE 56	22nd ST & MIDWEST RD	22nd ST & OAKBROOK PLAZA	22nd ST & MACARTHUR DRIVE	22nd ST & PARKVIEW DR	22nd ST & IL RTE 83	INTER-CONNECT	EMERGENCY VEHICLE PREEMPTION	80% FED 10% STATE 10% OAK BROOK	80% FED 10% STATE 10% OAKBRK TERR	100% OAK BROOK	100% OAK BROOK							
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% STATE 10% DUPAGE COUNTY	100% OAK BROOK	100% OAK BROOK	100% OAK BROOK	100% OAK BROOK	80% FED 20% STATE	100% OAK BROOK	80% FED 10% STATE 10% OAK BROOK	80% FED 10% STATE 10% OAKBRK TERR	100% OAK BROOK	100% OAK BROOK							
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,561	J000-2A	Y030-1E	Y003	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	SFTY-1B	SFTY-1B	Y060	J000-2A			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	890																							
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	319																							
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,102																							
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	313																							
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	2,330																							
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	53,908																							
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	18,270																							
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	1,227																							
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	5,696																							
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	1,600																							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,464																							
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	3,128																							
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	22,439																							
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3,892																				**			
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1																				**			
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1																				**			
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	3,900		52				1,095	504	637	554	554	220	64	220										
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	323						84		35	52	52	25	50	25							**			
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	299						45	40	18	39	39	39		39										
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	389						143	10	73	53	53		57								**			
* 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	60						10	10	10	10	10		10											
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	2,438			783			407	200	229	335	335		149											
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	686						66					270		270										
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	2,649						590	575	396	478	478		132											
* 81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	227						92						135											
* 81400100	HANDHOLE	EACH	36			1			8	5	3	5	5	2	5	2							**			
* 81400200	HEAVY-DUTY HANDHOLE	EACH	24				1		2	4	5	4	4		4											
* 81400300	DOUBLE HANDHOLE	EACH	13						4	3	2	2	2													
* 81603165	UNIT DUCT, 600V, 3-1C NO.6, 1/2" DIA. POLYETHYLENE	FOOT	5,865			5,865																				
* 81701345	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/2" NO. 3/0	FOOT	100			100																				
* 81800330	AERIAL CABLE, 3-1/2" NO. 6 WITH MESSENGER WIRE	FOOT	1,000			1,000																				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	9,273			4,877			894	564	773	708	708	284	181	284										
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	31			31																				
* 83050910	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-15 FT. MAST ARMS	EACH	2			2																				
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	219			219																				
* 83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	14			14																				
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	33			33																				
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	10			10																				
* 84200804	REMOVE POLE FOUNDATION	EACH	10			10																				
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	6						6																	
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	6						1	1	1	1	1		1											
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	6						1	1	1	1	1		1											
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	5,256						425	1,526	632	695	767	767		444										

\* SPECIALTY ITEM      \*\* Y030-1E 100% OAK BROOK  
 NP NON-PARTICIPATING ITEM      % Y080

FILE NAME =	USER NAME = jmgolamba	DESIGNED - JMG	REVISED -
g:\CH07\0061\Road\Sheets\0160012-SHT-50.dgn		DRAWN - BAW	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED - JRH	REVISED -
	PLOT DATE = 4/2/2010	DATE - 4/1/2010	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SHEET NO. 7 OF 362 SHEETS

F.A. RTE. 1453	SECTION 55WRS	COUNTY	TOTAL SHEETS 362	SHEET NO. 7
CONTRACT NO. 60D12		FED. ROAD DIST. NO. 7 [ILLINOIS] FED. AID PROJECT		