

8. SCHEDULE OF TEMPORARY PAVEMENT

FROM	TO	X0712400 TEMP PAVEMENT SQ YD		44000100 PAVEMENT REM SQ YD
		STAGE 1	STAGE 2	
22ND STREET				
200+00	212+00	453		453
212+00	224+00	3,013	3,676	6,689
224+00	236+00	3,427	1,267	4,694
236+00	248+00	2,678	1,667	4,345
248+00	261+00	1,785	1,152	2,937
261+00	273+00	1,309	2,913	4,222
273+00	286+00	1,134	918	2,052
BUTTERFIELD ROAD				
12+00	26+00	775	263	1,038
MIDWEST ROAD				
44+00	70+00	188		188
TOTAL BY STAGE		14,762	11,856	
TOTAL		26,618		26,618

SEE PCC PVMT
SCHEDULE FOR
OVERALL TOTAL
(SCHEDULE 5)

9. SCHEDULE OF STORM SEWER REMOVAL

FROM	TO	55100200 STORM SEWER REM 6 FOOT	55100300 STORM SEWER REM 8 FOOT	55100400 STORM SEWER REM 10 FOOT	55100500 STORM SEWER REM 12 FOOT	55100700 STORM SEWER REM 15 FOOT	55100900 STORM SEWER REM 18 FOOT	55101100 STORM SEWER REM 21 FOOT	55101200 STORM SEWER REM 24 FOOT	55101400 STORM SEWER REM 30 FOOT	55101600 STORM SEWER REM 36 FOOT	55039700 SS CLEANED FOOT	X0324752 STORM SEWER FILLED CU YD
22ND STREET													
200+00	212+00				322				42			125	20
212+00	224+00				853	67	95		316				
224+00	236+00		15	34	391	222	70			88			
236+00	248+00		126	94	1,084	382	94		735	86			
248+00	261+00				529	68	488	16	105				
261+00	273+00	20	108		1,058	430	108		456				
273+00	286+00				432			64	6			142	580
BUTTERFIELD ROAD													
12+00	20+00			17	103								173
MIDWEST ROAD													
53+00	65+00												394
TOTALS		20	249	145	4,772	1,189	855	80	1,660	174	267	1,147	20

10. SCHEDULE OF CURB AND GUTTER AND RELATED ITEMS

FROM	TO	44000300 CURB REM FOOT	44000500 COMB CURB GUTTER REM FOOT	44003100 MEDIAN REMOVAL SQ FT	44003800 MEDIAN SURF REMOVAL SQ FT	60600605 CONC CURB TB FOOT	60603800 COMB CC&G TB6.12 FOOT	60605000 COMB CC&G TB6.24 FOOT	60608600 COMB CC&G TB6.06 FOOT	60618320 CONC MEDIAN SURF 6 SQ FT	60619600 CONC MED TS86.12 SQ FT	60620000 CONC MED TS86.24 SQ FT	60624600 CORRUGATED MED SQ FT	42001300 PROTECTIVE COAT SQ YD
22ND STREET														
200+00	212+00		770		573			480			3,215		181	269
212+00	224+00	262	5,468	199	14,047	346	1,079	2,443	170	2,270	4,347		1,538	1,013
224+00	236+00	187	5,448		12,868	612	810	2,234		133	4,299		455	770
236+00	248+00	394	6,864		17,774	1,128	984	2,825	113	1,492	4,049		1,051	1,020
248+00	261+00	484	5,221	698	2,898	526	1,725	2,496			2,907		998	857
261+00	273+00	187	6,460		7,003	384	1,360	2,589	121	700	8,580		1,632	1,223
273+00	286+00	71	2,243	176	6,273	68	51	1,172			526	2,185	895	406
BUTTERFIELD ROAD														
12+00	20+00	234	1,512	67	2,727	188	349	1,001			1,445		306	315
MIDWEST ROAD														
53+00	65+00		412		559						882		140	57
TOTALS		1,819	34,398	1,140	64,722	3,252	6,378	15,240	404	4,595	30,249	2,185	7,196	5,930

SEE PCC PVMT
SCHEDULE FOR
OVERALL TOTAL
(SCHEDULE 5)

11. SCHEDULE OF SIDEWALK AND RELATED ITEMS

FROM	TO	44000600 SIDEWALK REM SQ FT	42400200 PC CONC SIDEWALK 5 SQ FT	42001300 PROTECTIVE COAT SQ YD	42400800 DETECTABLE WARNINGS SQ FT
22ND STREET					
200+00	212+00				
212+00	224+00	305	4,660	3,717	466
224+00	236+00		5,151	5,228	577
236+00	248+00	2,652	5,044	3,839	494
248+00	261+00	147	4,623	5,272	550
261+00	273+00	78	5,838	3,888	541
273+00	286+00		736	728	82
TOTALS		3,182	26,053	22,673	2,710

(OAKBROOK) (OAKBROOK TERRACE) SEE PCC PVMT SCHEDULE FOR OVERALL TOTAL (SCHEDULE 5) (OAKBROOK) (OAKBROOK TERRACE)

12. SCHEDULE OF DRAINAGE REMOVALS, ADJUSTMENTS AND RELATED ITEMS

FROM	TO	44004000 PAVED DITCH REMOVAL FOOT	50104400 CONC HDWL REM EACH	60250200 CB ADJUST EACH	60255500 MAN ADJUST EACH	60260100 INLETS ADJUST EACH	60500040 REMOV MANHOLES EACH	60500050 REMOV CATCH BAS EACH	60500060 REMOV INLETS EACH	Z0018500 DRAINAGE STR CLEANED EACH
22ND STREET										
200+00	212+00		7				1			8
212+00	224+00		13				1			26
224+00	236+00		11				1			17
236+00	248+00		6			1	13	2		21
248+00	261+00		5				2	1		18
261+00	273+00		13				3	2		34
273+00	286+00	96	1		1	9	1			16
BUTTERFIELD ROAD										
12+00	20+00		1	1						6
MIDWEST ROAD										
53+00	65+00									1
TOTALS		96	57	1	1	10	22	5	146	4