SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE SFTY-2A					
35200600	EARTH EXCAVATION	CU YD	46	46					
50102400	CONCRETE REMOVAL	CU YD	73	73					
50300100	FLOOR DRAINS	EACH	12	12					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	73	73					
50300260	BRIDGE DECK GROOVING	SQ YD	565	565					
50300300	PROTECTIVE COAT	SQ YD	752	752					
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6820	6820					
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	18	18					
50501110	STRUCTURAL STEEL REMOVAL	POUND	3320	3320					
50501130	STRUCTURAL STEEL REPAIR	POUND	2200	2200					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3080	3080					
50800515	BAR SPLICERS	EACH	56	56					
52000110	PREFORMED JOINT STRIP SEAL	FOOT	193	193					
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	18	18					
52100520	ANCHOR BOLTS, 1"	EACH	36	36					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	674	674					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	325	325					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	275	275					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1740	1740					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	37	37					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	28	28					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	540	540					
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	138	138					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	440	440					
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	1900	1900					
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	30	30					
X0712400	TEMPORARY PAVEMENT	SQ YD	208	208					
X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE SFTY-2A					
Z0006231	BRIDGE DECK HYDRO-SCARIFICATION 3 1/2"	SQ YD	553	553					
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	29	29					
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2					
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1					
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
X0326276	TEMPORARY LIGHTING FOR SINGLE LANE STAGING	L SUM	1	1					
X0326873	BRIDGE DECK LATEX CONCRETE OVERLAY, 3 1/2 INCHES	SQ YD	553	553					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	25	25					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ. YD.	292	292					
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	17	17					
78100300	REPLACEMENT REFLECTOR	EACH	20	20					
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	3	3					

* Specialty Items

Rev.

FILE NAME =	USER NAME = mldyja	DESIGNED -	REVISED -
c:\pw_work\pwidot\mldyja\d0018105\D0182209-sht-plan01.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/18/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0327	112 BR-I-1	WILL	28	3
		CONTRACT NO. 60H86		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		