

**SUMMARY OF QUANTITIES**

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	ROADWAY		BRIDGE		
				URBAN TOTAL QUANTITY	100% STATE	100% STATE	CONSTRUCTION TYPE CODE 1000-2A	X271-2A
	20200100	EARTH EXCAVATION	CU YD	25				
	28000510	INLET FILTERS	EACH	5	5			
	28100107	STONE RIPRAP, CLASS A4	SQ YD	30		30		
	28200200	FILTER FABRIC	SQ YD	30		30		
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	18	18			
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	15	15			
	42001300	PROTECTIVE COAT	SQ YD	396	396			
	42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	116	116			
	42100800	PAVEMENT REINFORCEMENT 9"	SQ YD	116	116			
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	300.0	300.0			
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	207	207			
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	87	87			
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100			
	48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	42	42			
	50102400	CONCRETE REMOVAL	CU YD	13.0		13.0		
	50157300	PROTECTIVE SHIELD	SQ YD	1,435		1,435		
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	14.3		14.3		
	50300260	BRIDGE DECK GROOVING	SQ YD	1,609		1,609		
	50300300	PROTECTIVE COAT	SQ YD	2,343		2,343		
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1190		1190		
	50800515	BAR SPLICERS	EACH	22		22		
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	66.0		66.0		
	58700300	CONCRETE SEALER	SQ FT	315		315		
	60600605	CONCRETE CURB, TYPE B	FOOT	63.0	63.0			
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	87.0	87.0			
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1			
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1			
	67000200	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4			
	67100100	MOBILIZATION	L SUM	1	1			
	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1			
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1			
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3			
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,544	1,544			
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	950	950			
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	840	840			

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	ROADWAY		BRIDGE		
				URBAN TOTAL QUANTITY	100% STATE	100% STATE	CONSTRUCTION TYPE CODE 1000-2A	X271-2A
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	840				
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	140		140		
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	930		930		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2		2		
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	15		15		
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	1		1		
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	68		68		
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1		1		
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,550		1,550		
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	17		17		
*	81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	209		209		
*	81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	5		5		
*	81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	2		2		
*	81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	861		861		
*	84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	4		4		
	X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4"	SQ YD	1,714		1,714		
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	77		77		
*	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3		3		
	X0324848	LIGHT POLE HANDHOLE COVER	EACH	1		1		
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	264		264		
	X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	3,000		3,000		
*	X0326323	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	7		7		
	X0326765	CLEANING AND PAINTING EXPOSED REBAR (SPECIAL)	SQ FT	297		297		
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1		1		
	X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	L SUM	1		1		
	Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	10.0		10.0		
	Z0006204	BRIDGE DECK HYDRO-SCARIFICATION, 1/2"	SQ YD	1,714		1,714		
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1		
	Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	9.8		9.8		
	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	12.5		12.5		
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5		5		
	Z0053750	RETROFIT CONCRETE PARAPET	FOOT	525		525		
	Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	2		2		
	Z0080255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW)	EACH	1		1		
	44-000700	APPROACH SLAB REMOVAL TEST LEVEL 2	SQ YD	13		13		
	Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE) TEST LEVEL 2	EACH	1		1		

\* Specialty Items