



LEGEND:

- ① THERMOPLASTIC PAVEMENT MARKING TYPE 1 - LINE 4" (WHITE EDGE LINES)
- ② THERMOPLASTIC PAVEMENT MARKING TYPE 1 - LINE 4" (YELLOW EDGE LINES)
- ③ THERMOPLASTIC PAVEMENT MARKING TYPE 1 - LINE 4" (WHITE, 10' DASH, 30' SKIP)
- ④ POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" (WHITE EDGE LINES)
- ⑤ POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" (YELLOW EDGE LINE)
- ⑥ POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" (WHITE, 10' DASH, 30' SKIP)
- ⑦ RAISED REFLECTIVE MARKERS
- ⑧ RAISED REFLECTIVE MARKERS (BRIDGE)
- C DRAINAGE STRUCTURE TO BE CLEANED

NOTES:

1. SEE IDOT DISTRICT 1 STANDARD TC-11 "RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" FOR PLACEMENT AND TYPE OF RAISED REFLECTIVE PAVEMENT MARKERS.
2. COMBINATION CONCRETE CURB AND GUTTER SHOULD BE CONSTRUCTED SO GUTTER ELEVATION MATCHES PROPOSED OVERLAY PAVEMENT ELEVATION AND CURB ELEVATION TIES INTO EXISTING CURB.
3. PROPOSED PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH ELEVATION SHOULD MATCH THAT OF THE ADJACENT PROPOSED CURB.
4. SEE IDOT DISTRICT 1 STANDARD TC-13 "DISTRICT ONE TYPICAL PAVEMENT MARKINGS" FOR ADDITIONAL PAVEMENT MARKING INFORMATION.

* THE EXPANSION JOINT DETAILED BETWEEN THE APPROACH SLAB AND APPROACH PAVEMENT CONNECTOR IN HIGHWAY STANDARD 420401 IS TO BE OMITTED. EXISTING REINFORCEMENT REMAINING ACCORDING TO THE ROADWAY REMOVAL PLAN IS TO BE CLEANED, STRAIGHTENED AND INCORPORATED IN THE PROPOSED CONSTRUCTION. THIS JOINT SHALL INSTEAD BE TREATED AS A LONGITUDINAL CONSTRUCTION JOINT AS DETAILED IN HIGHWAY STANDARD 420001. COST INCLUDED IN BRIDGE APPROACH PAVEMENT CONNECTOR (PCC).

** CONCRETE CURB, TYPE B TO BE ATTACHED TO EXISTING APPROACH SLAB OR BRIDGE APPROACH PAVEMENT CONNECTOR (PCC). SEE IDOT STANDARD 606001 FOR DETAILS.

FILE NAME =	DESIGNED - EJA	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	WB HIGGINS ROAD ROADWAY & PAVEMENT MARKING PLAN			F.A.U. RTE. 3531	SECTION 1515.1-1	COUNTY COOK	TOTAL SHEETS 35	SHEET NO. 7
USER NAME =	DRAWN - EJA	REVISED -			SCALE: 1" = 20'	SHEET NO. 1 OF 1 SHEETS	STA. 42+10.50 TO STA. 48+87.50	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 60J58		
PLOT DATE = 03/22/2010	CHECKED - AJP	REVISED -			DATE - 3/19/10	REVISED -						