

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	1000-2A STATE QUANTITY
20200600	EXCAVATING AND GRADING SHOULDER	UNIT	2	2
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19
40600300	AGGREGATE (PRIME COAT)	TON	96	96
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	36	36
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,344	1,344
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	311	311
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	550	550
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,017	2,017
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	24,007	24,007
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	30	30
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2,454	2,454
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	887	887
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	730	730
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	350	350
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	185	185
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	204	204
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	443	443
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	6	6
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3
63200310	GUARDRAIL REMOVAL	FOOT	150	150
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,109	4,109
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	609	609
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41,089	41,089
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,557	2,557
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,655	1,655
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	533	533
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	304	304
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,545	20,545
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,278	1,278
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	828	828
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	313	313
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	178	178
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	89	89
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	768	768
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
X2503100	MOWING	UNIT	9	9
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	283	283
X0325917	TURF ESTABLISHMENT	SQ YD	96	96
20800150	TRENCH BACKFILL	CU YD	19	19
550A0050	STORM SEWER, CLASS A, TYPE I 12"	FOOT	39	39
550A0070	STORM SEWER, CLASS A, TYPE I 15"	FOOT	16	16
55039700	STORM SEWER TO BE CLEANED	FOOT	742	742
Z0018300	DRAINAGE STRUCTURE REPAIR	EACH	4	4
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	17	17

*Specialty Items

Rev.

H:\Jobs\2009\20090223-22\CAD\Site\ogn\00\060606-shr-500.dgn
 2/12/2010 4:24:46 PM

FILE NAME *	USER NAME * USER.	DESIGNED - EF	REVISED - EF 02-12-2010	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 176 - US 41 TO SHERIDAN ROAD SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE * 50.0000' / IN.	CHECKED - RS	REVISED -					1238	C-RS-9	LAKE	19	3
	PLOT DATE * 2/12/2010	DATE - 01/13/2010	REVISED -		SCALE: NTS	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 60J66			
								[ILLINOIS] FED. AID PROJECT				