

SUMMARY OF QUANTITIES				URBAN				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES				URBAN				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE	1000-2A					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE	1000-2A								
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	840	840						70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1									
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	600	600						70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	54	54						70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10000	10000									
40600300	AGGREGATE (PRIME COAT)	TON	272	272						70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	865	865									
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	102	102						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	29294	29294									
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2806	2806						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4694	4694									
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	900	900									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	607	607						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	700	700									
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	170	170						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2500	2500									
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6664	6664					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	865	865										
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	4000	4000					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	29294	29294										
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	68003	68003					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	46940	46940										
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	800	800					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	900	900										
44000600	SIDEWALK REMOVAL	SO FT	4000	4000					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	700	700										
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	340	340					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	500	500										
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	680	680					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	500	500										
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	340	340					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4										
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	340	340					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	25	25										
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	680	680					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1										
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	340	340					21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	350	350										
50300300	PROTECTIVE COAT	SO YD	50	50					25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7	7										
55039700	STORM SEWERS TO BE CLEANED	FOOT	1000	1000					25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7	7										
60250200	CATCH BASINS TO BE ADJUSTED	EACH	24	24					25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7	7										
60250300	CATCH BASINS TO BE ADJUSTED (SPECIAL)	EACH	12	12					25200200	SUPPLEMENTAL WATERING	UNIT	18	18										
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	15	15					44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	800	800										
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10					42300200	PORTLAND CEMENT CONCRETE DRIVEWAY 6"	SO YD	600	600										
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	2	2					42300400	PORTLAND CEMENT CONCRETE DRIVEWAY 8"	SO YD	420	420										
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	2	2					44000200	DRIVEWAY REMOVAL	SO YD	2420	2420										
60603000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-G, 12	FOOT	800	800																			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																			
67100100	MOBILIZATION	L SUM	1	1																			

FILE NAME =	USER NAME = gysnst	DESIGNED -	REVISED -
PLLOT SCALE = 50,0000' / IN.	CHECKED -	DRAWN -	REVISED -
PLLOT DATE = 2/9/2010	DATE -		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CENTRAL AVENUE
SUMMARY OF QUANTITIES

F.A.P. RTE. 366	SECTION 0203 RS-2	COUNTY COOK	TOTAL SHEETS 23	SHEET NO. 3
SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 60J99	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.