

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM	UNIT	100% STATE TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY-URBAN I000	ROADWAY-RURAL I000
20400800	FURNISHED EXCAVATION	CU YD	26	20	6
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	26720	21842	4878
40600300	AGGREGATE (PRIME COAT)	TON	302	247	55
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	44	8	36
40600725	POLYMERIZED LEVELING BINDER (HAND METHOD), N50	TON	73	13	60
40600895	CONSTRUCTING TEST STRIP	EACH	2		2
40600990	TEMPORARY RAMP	SQ YD	610	156	454
40603510	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	12644	2303	10341
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	677	143	534
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	48	48	
42400800	DETECTABLE WARNINGS	SQ FT	32	32	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	72106		72106
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	74034	26611	47423
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	5192	1105	4087
44000600	SIDEWALK REMOVAL	SQ FT	80	80	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1970		1970
66700095	PERMANENT SURVEY MARKERS	EACH	6		6
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	1	1
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	2	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16114	2809	13305
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	324	324	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	157940	13810	144130
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13428	2340	11088
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1789	312	1477
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	324	324	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	157940	13810	144130
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	13428	2340	11088
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	671	116	555
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	671	116	555
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	6322	1152	5170
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
X0322729	MATERIAL TRANSFER DEVICE	TON	18,966	3,455	15,511

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = braboypc	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>DETAILS</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca\pwork\pwork\braboypc\d0118886\DETAILS.dgn	PLLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -					627	(M,I,U,N,W,I,Z)RS-3	LASALLE	9	3
PLLOT DATE = Dec 31, 2009 - 01:36:04 PM	DATE -	CHECKED -	REVISED -		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 66598				
					ILLINOIS FED. AID PROJECT							