

SIDE ROADS & ENTRANCES										
LOCATION	STATION	RT/LT	TYPE	HMA SURF REM	VARINCIDENTAL	HMA	BIT MATLS	AGG PR CT	TEMP RAMP	FURN EX*
				DEPTH**	SURF		PR CT			
				SO YD	TON		GAL	TON	SO YD	CU YD
	641+34	LT	MB	40.9	5.2		3.3	0.1		
	641+34	RT	PE	50.6	6.4		4.0	0.1		
	657+15	LT	PE	27.3	3.5		2.2	0.1		
	657+15	LT	MB	40.9	5.2		3.3	0.1		
	661+22	LT	PE	65.7	8.3		5.3	0.1		
E 950TH RD	700+79	RT	SR	107.6	13.6		8.6	0.2	35.9	2
	702+75	RT	PE	40.2	5.1		3.2	0.1		
	703+90	RT	PE	34.1	4.3		2.7	0.1		
	708+66	LT	PE	25.1	3.2		2.0	0.1		
	708+66	LT	MB	40.9	5.2		3.3	0.1		
	710+56	LT	PE	30.1	3.8		2.4	0.1		
	745+24	RT	PE	68.2	8.6		5.5	0.1		
	758+59	LT	CE	43.1	5.5		3.4	0.1		
	769+75	RT	PE	43.1	5.5		3.4	0.1		
	771+26	RT	PE	29.1	3.7		2.3	0.1		
	771+26	RT	MB	40.9	5.2		3.3	0.1		
	772+21	RT	PE	31.9	4.1		2.6	0.1		
	772+21	RT	MB	40.9	5.2		3.3	0.1		
	774+87	RT	PE	27.3	3.5		2.2	0.1		
	774+87	RT	MB	40.9	5.2		3.3	0.1		
E 1069TH RD	777+56	RT	SR	101.2	12.8		8.1	0.2	33.5	2
E 1101ST RD	804+30	RT	SR	72.5	9.2		5.8	0.1	23.9	2
E 1101ST RD	805+61	RT	SR	109.1	13.8		8.7	0.2	37.1	2
	809+61	RT	PE	30.9	3.9		2.5	0.1		
	839+83	RT	PE	29.1	3.7		2.3	0.1		
	850+85	RT	PE	71.4	9		5.7	0.1		
	857+05	LT	PE	39.5	5		3.2	0.1		
	857+05	RT	PE	43.1	5.5		3.4	0.1		
	867+00	RT	PE	32.3	4.1		2.6	0.1		
	881+20	RT	PE	32.3	4.1		2.6	0.1		
	882+84	RT	PE	27.3	3.5		2.2	0.1		
	898+32	RT	PE	28.7	3.7		2.3	0.1		
	898+32	RT	MB	40.9	5.2		3.3	0.1		
	904+79	LT	PE	30.9	3.9		2.5	0.1		
	904+79	RT	MB	40.9	5.2		3.3	0.1		
	919+52	RT	PE	68.2	8.6		5.5	0.1		
	919+52	RT	MB	40.9	5.2		3.3	0.1		
	919+52	RT	MB	40.9	5.2		3.3	0.1		
	947+31	LT	PE	46.6	5.9		3.7	0.1		
	947+31	RT	MB	40.9	5.2		3.3	0.1		
E 2151ST RD	947+31	RT	SR	100.5	12.7		8.0	0.2	33.5	2
	938+28	RT	PE	46.6	5.9		3.7	0.1		
	952+13	LT	PE	39.5	5		3.2	0.1		
	952+13	RT	MB	40.9	5.2		3.3	0.1		
	959+22	LT	PE	32.3	4.1		2.6	0.1		
	959+22	RT	MB	40.9	5.2		3.3	0.1		
	961+02	LT	PE	28.7	3.7		2.3	0.1		
	961+02	RT	MB	40.9	5.2		3.3	0.1		
	965+52	LT	PE	25.1	3.2		2.0	0.1		
	965+52	RT	MB	40.9	5.2		3.3	0.1		
	976+87	LT	PE	28.7	3.7		2.3	0.1		
	976+87	RT	MB	40.9	5.2		3.3	0.1		
E 1409TH RD	978+67	RT	SR	93.3	11.8		7.5	0.2	33.5	2
	987+23	RT	PE	28.7	3.7		2.3	0.1		
	987+23	RT	MB	40.9	5.2		3.3	0.1		
	987+27	LT	PE	28.7	3.7		2.3	0.1		
	987+27	RT	MB	40.9	5.2		3.3	0.1		
	990+35	LT	PE	25.1	3.2		2.0	0.1		
	990+35	RT	MB	40.9	5.2		3.3	0.1		
	993+04	LT	PE	25.1	3.2		2.0	0.1		
	993+04	RT	MB	40.9	5.2		3.3	0.1		
	995+08	RT	PE	35.9	4.6		2.9	0.1		
	995+08	RT	MB	40.9	5.2		3.3	0.1		
	995+70	LT	PE	44.8	5.7		3.6	0.1		
	995+86	RT	PE	32.3	4.1		2.6	0.1		
	1002+72	LT	PE	35.9	4.6		2.9	0.1		
	1002+72	RT	MB	40.9	5.2		3.3	0.1		
	1004+95	LT	PE	25.1	3.2		2.0	0.1		
	1004+95	RT	MB	40.9	5.2		3.3	0.1		
	1006+07	LT	PE	32.3	4.1		2.6	0.1		
	1010+79	LT	PE	32.7	4.2		2.6	0.1		
	1010+79	RT	MB	40.9	5.2		3.3	0.1		
DEER PARK RD	1010+79	RT	SR	150.7	19		12.1	0.3	50.2	2
	1022+86	LT	SR	143.5	18.1		11.5	0.3		
	1030+28	LT	CE	46.6	5.9		3.7	0.1		
N 2650TH RD	1030+28	RT	SR	86.1	10.9		6.9	0.2	28.7	2
	1032+54	RT	MB	40.9	5.2		3.3	0.1		
	1033+72	LT	PE	25.1	3.2		2.0	0.1		
	1063+05	RT	PE	44.3	5.6		3.5	0.1		
4H RD	1071+29	RT	SR	95.7	12.1		7.7	0.2	47.8	2
4H RD	1071+32	RT	SR	344.4	43.4		27.6	0.7	38.3	2
RURAL TOTAL				4086.7	533.952		326.936	8.1734	362.4	20
SWANSON ST	1136+61	RT	SR	202.1	25.5		16.2	0.4	31.1	2
IRWIN ST	1139+37	RT	SR	144.7	18.3		11.6	0.3	26.3	2
PONTIAC LN	1143+50	LT	SR	157.9	19.9		12.6	0.3	28.7	2
ALLEN PARK RD	1150+59	LT	SR	300	37.8		24.0	0.6	30	
SPRING STREET	1153+30	RT	SR	300	37.8		24.0	0.6	30	
URBAN TOTAL				1104.7	143.479		88.376	2.2094	146.1	6
GRAND TOTALS				5191.4	677.431		415.312	10.3828	508.5	26

SIDEWALK (ALL URBAN)			
LOCATION	SIDEWALK REMOVAL	DETECTABLE WARNINGS	PCC SIDEWALK, 4"
LOCATION	SQ FT	SQ FT	SQ FT
PONTIAC LANE			
NE QUAD	20	8	12
NW QUAD	20	8	12
ALLEN PARK RD			
NE QUAD	20	8	12
NW QUAD	20	8	12
TOTAL	80	32	48

PERMANENT SURVEY MARKERS	
LOCATION	PERMANENT SURVEY MARKERS
LOCATION	EACH
NE CORNER SECTION 28	1
NW CORNER, NE 1/4 SECTION 28	1
E 1/4 CORNER SECTION 19	1
CENTER OF SECTION 21	1
CENTER OF SECTION 20	1
W 1/4 CORNER, SECTION 21	1
TOTAL	6

ALL SECTION CORNERS TO BE ESTABLISHED BY LICENCED LAND SURVEYOR AND REGISTERED AT THE COUNTY COURT HOUSE-INCLUDED IN THE COST OF PERMANENT SURVEY MARKERS  
SEE COMMITMENT FILE FOR TIE POINTS

\*PLACE FURNISHED EX AROUND SIDERAOD RADII. THIS AREA TO BE SEEDED, FERTILIZED AND MULCHED- NOT PAID FOR SEPERATELY BUT INCLUDED IN THE COST OF FURNISHED EXCAVATION  
STA 628+50 TO 1072+00 RURAL  
STA 1172+00 TO 1165+59 URBAN  
\*\* PAY FOR AS VARIABLE DEPTH EVEN IF ENTRANCE IS CONSTANT 1-1/2" HMA SURF REMOVAL

FILE NAME =	USER NAME = braboypa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pw\work\pwsdat\braboypa\0118886\DETA	ILLS.dgn	DRAWN -	REVISED -			627	(M,I,U,N,W,I,Z)RS-3	LASALLE	9	6	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 66598					
	PLOT DATE = Dec 31, 2009 - 01:35:57 PM	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					