

100% STATE

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	CONSTRUCTION CODE: 1000	
		UNIT	TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	16
25100630	EROSION CONTROL BLANKET	SQ YD	336
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	21
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9460
40600300	AGGREGATE (PRIME COAT)	TON	303
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22
40600535	LEVELING BINDER (HAND METHOD), N70	TON	36
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2974
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	190
40600990	TEMPORARY RAMP	SQ YD	185
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5969
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	234
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	70780
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2267
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3213
48203100	HOT-MIX ASPHALT SHOULDERS	TON	120
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122.4
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	59053
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4690
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	66
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	778
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	59053
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	4690
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	122.4
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	66
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	292
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	275
X0322729	MATERIAL TRANSFER DEVICE	TON	8943
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

• SPECIALTY ITEMS

FILE NAME =	USER NAME = corcoranlm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\PWIDOT\CORCORANLM\dms61037\366836-sheets.dgn		DRAWN -	REVISED -			573	(116)RS-2	DEKALB	11	3	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 66836					
PLOT DATE = Feb 04, 2010 - 01:48:10 PM		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.