

MAINLINE SCHEDULE													
STATION TO STATION	AREA	HMA SURF REM	HMA SURF REM	HMA SURF REM	BIT MATL PRIME COAT	AGG PRIME COAT	MIX FOR CRACKS JTS & FLGWYS	LEVEL BINDER (HM) N70	LEVEL BINDER (MM) N70	HMA SURF CRSE MIX "D" N70	TEMP RAMP	SHORT TERM PAVT MARKING	AGG SHLDS TY B
		1 1/2" SQ YD	2 1/4" SQ YD	BUTT JT SQ YD	GALLON	TON	TON	TON	TON	TON	SQ YD	FOOT	TON
325+83 TO 326+13	80			80	11	2	0.1	0.1	4	7	14	9	5
326+13 TO 347+70	5752	5752			748	24	1.8	2.9	242	484		647	312
347+70 TO 355+13	2064		2045		269	10	0.7	1.1	87	174	21	223	54
355+13 TO 360+13	Bridge Omission												
360+13 TO 360+93	223		222		29	2	0.1	0.2	10	19	21	24	12
360+93 TO 374+00	3279	3279			427	14	1	1.7	138	276		392	189
374+00 TO 433+30	18449	18449			2399	74	5.6	9.3	775	1550		1779	856
433+30 TO 434+10	249	249			33	2	0.1	0.2	4	21	16	24	12
434+10 TO 434+20	Railroad Omission												
434+20 TO 435+00	249	249			33	2	0.1	0.2	4	21	16	24	12
435+00 TO 485+54	15724	15724			2045	64	4.8	7.9	661	1321		1516	730
485+54 TO 492+90	2290	2290			298	10	0.7	1.2	97	193		221	
492+90 TO 556+40	19756	19756			2569	80	6	9.9	830	1660		1905	917
556+40 TO 563+95	2769	2769			360	12	0.9	1.2	117	233		227	109
563+95 TO 564+25	110			110	15	2	0.1	0.1	5	10	19	9	5
TOTALS		68517	2267	190	9236	298	22	36	2974	5969	107	7000	3213

PAVEMENT MARKING SCHEDULE							
STATION TO STATION	PAINT PAVEMENT MARKING			PREFORMED PLASTIC PAVEMENT MARKING, TYPE B		RAISED REFL PAVT MARKER	RAISED REFL PAVT MARKER REMOVAL
	YELLOW 4" FOOT	WHITE 4" FOOT	YELLOW 6" FOOT	WHITE 24 FOOT	LETTERS & SYMBOLS SQ FT	AMBER EACH	EACH
	325+83 TO 564+25		46508	4690			292
EBL RXR				22	61.2		
EBL STOP BAR				11			
WBL STOP BAR				11			
WBL RXR				22	61.2		
EASTBOUND (NO PASSING ZONE)							
325+83 TO 385+37	5377						
426+30 TO 434+92	862						
WESTBOUND (NO PASSING ZONE)							
329+83 TO 392+73	5703						
433+58 TO 439+71	603						
SUB TOTALS	12545	46508	4690	66	122.4	292	275
TOTALS		59053	4690	66	122.4	292	275

TEMPORARY PAVEMENT MARKING SCHEDULE					
STATION TO STATION	TEMPORARY PAVEMENT MARKING				
	YELLOW 4" FOOT	WHITE 4" FOOT	YELLOW 6" FOOT	WHITE 24 FOOT	LETTERS & SYMBOLS SQ FT
	325+83 TO 564+25		46508	4690	
EBL RXR				22	61.2
EBL STOP BAR				11	
WBL STOP BAR				11	
WBL RXR				22	61.2
EASTBOUND (NO PASSING ZONE)					
325+83 TO 385+37	5377				
426+30 TO 434+92	862				
WESTBOUND (NO PASSING ZONE)					
329+83 TO 392+73	5703				
433+58 TO 439+71	603				
SUB TOTALS	12545	46508	4690	66	122.4
TOTALS		59053	4690	66	122.4