

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	48RS-2	PEORIA KNOX	26	7

LOCATION	WIDTH	AVRG. WIDTH	HOT-MIX ASPHALT SURF REMOVAL-BUTT JOINT	TEMP RAMP
	FT	FT	SQ YD	SQ YD
PEORIA COUNTY				
STARTING STA. 1+10 TO 1+30	24.00	24.00	80.00	13.33
STA. 108+15 TO 108+45	24.00	24.00	80.00	13.33
STA. 107+20 Korth Rd	25.00	48.00	160.00	13.89
STA. 212+25 Grand Chapel Rd	22.00	22.00	73.33	12.22
STA. 109+71 TO 110+01	24.00	24.00	80.00	13.33
KNOX COUNTY				
STA. 235+20 TO 235+50	26.00	26.00	86.67	14.44
STA. 236+76 TO 237+06	26.00	26.00	86.67	14.44
EAST LEG ENDING STA. 297+20 TO 297+50	210.00	210.00	700.00	116.67
WEST LEG STA. 297+60 TO 297+90	180.00	180.00	600.00	100.00
PEORIA COUNTY			473.33	53.89
KNOX COUNTY			1,473.33	257.78
Total			1,947	312

URETHANE PAVEMENT MARKING SCHEDULE			
LOCATION	LINE 4"		LINE 24 "
	WHITE	YELLOW	WHITE
	FOOT	FOOT	FOOT
PEORIA COUNTY			
STA. 1+10 TO 212+25	41,945	24,155	
KNOX COUNTY			
STA. 212+25 TO 297+90	19,360	16,559	24.00
Total	61,305	40,714	24
NOTE : PRIOR TO PLACING CENTERLINE STRIPING, CONTACT THE DISTRICT BUREAU OF OPERATION FOR A " NO PASSING ZONE " EVALUATION			

RATES:

FOR ALL HOT MIXES: 112 lbs/Sq.Yd.in.

FOR AGGREGATE SHOULDERS TYPE B: 2.05 ton/cu.yd

FOR BIT MATLS (PRIME COAT): 0.004 ton/gal

FOR AGG (PRIME COAT):

-ON GRANULAR BASE: 0.5 GAL/SQ. YD.

-ON EXIST PVT: 4 LBS/SQ. YD.

-ON EXIST. PVT.: 0.05 GAL/SQ.YD.

-ON COLD MILLED SURF: 4 LBS/SQ.YD.

-ON COLD MILLED AREA: 0.1 GAL/SQ.YD.

-ON NEW PVT: 2 LBS/SQ.YD.

-ON NEW PAV'T: 0.03 GAL/SQ.YD.

TEMPORARY PAINT PAVEMENT MARKING SCHEDULE

LOCATION	LINE 4"		LINE 24 "
	WHITE	YELLOW	WHITE
	FOOT	FOOT	FOOT
PEORIA COUNTY			
STA. 1+10 TO 212+25	41,945	24,155	
KNOX COUNTY			
STA. 212+25 TO 297+90	19,360	16,559	24.00
Total	61,305	40,714	24

SCHEDULE OF QUANTITIES