

100% STATE

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE															
					1000-2A ROADWAY RURAL	X281-2A S.N. 001-0067	X231-2A S.N. 001-0064 S.N. 001-0065	X271-2A S.N. 001-0058	X271-2A S.N. 001-0060	X031-2A S.N. 001-0055 S.N. 001-0056	X031-2A S.N. 001-0062 S.N. 001-0063	X271-2A S.N. 001-0061	X271-2A S.N. 001-0044							
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)		UNIT	100	100															
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)		UNIT	100	100															
20100500	TREE REMOVAL, ACRES		ACRE	0.5	0.5															
20200100	EARTH EXCAVATION	*	CU YD	912	912															
** 20200200	ROCK EXCAVATION	*	CU YD	300	300															
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		CU YD	14	14															
20300100	CHANNEL EXCAVATION		CU YD	500	500															
20400800	FURNISHED EXCAVATION		CU YD	895	895															
20600110	GRANULAR EMBANKMENT, SPECIAL		TON	55	55															
21400100	GRADING AND SHAPING DITCHES	*	FOOT	810	810															
25000200	SEEDING, CLASS 2		ACRE	0.75	0.75															
25000400	NITROGEN FERTILIZER NUTRIENT		POUND	65	65															
25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	65	65															
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	65	65															
25000700	AGRICULTURAL GROUND LIMESTONE		TON	1.5	1.5															
25100115	MULCH, METHOD 2		ACRE	0.75	0.75															
25101005	HEAVY DUTY EXCELSIOR BLANKET	*	SQ YD	1000	1000															
28000500	INLET AND PIPE PROTECTION		EACH	25	25															
28001000	AGGREGATE (EROSION CONTROL)		TON	300	300															
28100707	STONE DUMPED RIPRAP, CLASS A4	*	SQ YD	3545	3545															
28200200	FILTER FABRIC		SQ YD	3748	3545								203							
28400100	GABIONS		CU YD	144									144							
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A		TON	851	851															
31200100	STABILIZED SUB-BASE 4"		SQ YD	120	120															
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	*	SQ YD	152	152															
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	*	SQ YD	3003	3003															
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	*	SQ YD	2232	2232															
40200800	AGGREGATE SURFACE COURSE, TYPE B		TON	5	5															
40600200	BITUMINOUS MATERIALS (PRIME COAT)		TON	302.4	302.4															
40600300	AGGREGATE (PRIME COAT)		TON	1180	1180															

** SPECIALTY ITEMS

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
o:\pwwork\pvi001\LAUGHLINR1\003-0672A09-ah1-sum0.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0002' / 1"		CHECKED -	REVISED -
PLOT DATE = Feb-01-2010 08:56:00AM		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: none SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	1-(1,2,3,4,5)RS	ADAMS	165	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72A09	