

CURB & GUTTER / MEDIAN SCHEDULE

STATION TO STATION	SIDE	44000100	44000500	44002020	44003100	20200100	20600110	31100100	35300300	60608600		60610400	60618300	60622400		60623200
		PAVEMENT REMOVAL	COMBINATION CURB & GUTTER REMOVAL	CONC MEDIAN SURFACE REMOVAL	MEDIAN REMOVAL	EARTH EXCAVATION	GRANULAR EMBANKMENT SPECIAL, 10"	SUB-BASE GRAN MATL TYPE A, 6"	PCC BASE COURSE 8"	COMBINATION CURB & GUTTER		CONC MEDIAN SURFACE 4 INCH	CONCRETE MEDIAN			
		SQ YD	FOOT	SQ FT		CU YD	TON		SQ YD	FOOT			TYPE SM-6.06	TYPE SM-6.24	SQ FT	
RAMP A IL 57																
28+01.81	28+28.94	LT & RT	10.3	74.6	257.5		16.5	7.1	11.3	33.1	13.3	36.0	112.0			
RAMP C IL 57																
25+84.80	26+10.94	LT & RT	9.3	70.6	231.9		15.7	5.9	10.7	31.4	11.8	33.2	92.7			
RAMP A IL 96																
21+03.31	21+22.64	LT & RT	4.8	51.0	108.3		4.9	4.4	3.3	9.7	39.7		70.1			
RAMP C IL 96																
21+03.29	21+22.62	LT & RT	4.8	51.0	108.3		4.9	4.6	3.3	9.7	39.7		72.2			
IL 57																
43+15.50	43+23.50	LT & RT		15.5			1.4									71.2
43+80.71	44+06.60	RT				155.5	2.1		4.3	12.6						42.0
56+50.67	56+58.67	LT & RT		15.5			1.4									71.2
57+19.50	57+45.72	RT				157.3	2.1		4.4	12.8						42.0
IL 96																
43+74.05	43+90.08	LT & RT	5.6	23.3	62.9		4.2	4.8			20.3		75.2	41.0		
44+46.56	45+23.89	RT	0.9	156.0	274.3		18.4	9.0	7.2	21.1	91.1		141.7	26.6		
54+76.16	55+53.44	LT	0.9	156.0	274.3		18.4	9.0	7.2	21.1	91.1		141.7	26.6		
56+09.93	56+34.00	LT & RT	5.6	39.8	151.9		9.1	10.4			36.8		164.2	41.0		
TOTALS			42.2	653.3	1469.4	312.8	99.1	55.0	51.8	151.6	343.8	69.2	869.8	135.2	226.4	
USE			43	654	1470	313	100	55	52	152	344	70	870	136	227	

TEMPORARY RAMP

STATION TO STATION	SIDE	DEPTH (INCHES)	PAVEMENT WIDTH	SHOULDER WIDTH	SQ YD	
FAI 172						
16+40.03	16+50.03	LT	1.5	24	16	44.4
76+00.00	76+10.00	RT	1.5	24	16	44.4
119+42.00	119+52.00	RT	2	42	12	60.0
119+42.00	119+52.00	LT	2	40	12	57.8
121+61.50	121+71.50	RT	2	38	12	55.6
121+61.50	121+71.50	LT	2	29	12	45.6
147+99.01	148+09.01	RT	2	24	16	44.4
148+73.03	148+83.03	LT	2	24	16	44.4
151+40.51	151+50.51	RT	2	24	16	44.4
152+14.53	152+24.53	LT	2	24	16	44.4
178+87.50	178+97.50	LT	2	24	16	44.4
179+77.31	179+87.31	RT	2	24	16	44.4
181+69.73	181+79.73	LT	2	24	16	44.4
182+77.40	182+87.40	RT	2	24	16	44.4
75+86.50	75+99.00	LT	3.75	24	16	55.6
78+87.50	79+00.00	RT	3.75	24	16	55.6
RAMP A IL 57						
27+27.44	27+39.94	LT	3.75	16	10	36.1
RAMP B IL 57						
1+34.08	1+46.58	LT	3.75	16	10	36.1
RAMP C IL 57						
25+10.08	25+22.58	LT	3.75	16	10	36.1
RAMP D IL 57						
1+43.59	1+56.09	LT	3.75	16	10	36.1
RAMP A IL 96						
20+62.26	20+72.26	LT	1.5	16	10	28.9
RAMP B IL 96						
1+04.46	1+14.46	LT	1.5	16	10	28.9
RAMP C IL 96						
20+62.12	20+72.12	LT	1.5	16	10	28.9
RAMP D IL 96						
1+04.46	1+14.46	LT	1.5	16	10	28.9
IL 57						
30+15.00	30+25.00	LT & RT	1.5	24	14	42.2
59+25.00	59+35.00	LT	1.5	26	10	40.0
59+25.00	59+35.00	RT	1.5	14	10	26.7
IL 96						
32+00.00	32+10.00	LT & RT	1.5	28	8	40.0
48+50.99	48+60.99	RT	1.5	14	8	24.4
48+54.17	48+64.17	LT	1.5	14	8	24.4
51+30.83	51+40.83	RT	1.5	14	8	24.4
51+34.01	51+44.01	LT	1.5	14	8	24.4
57+14.33	57+24.33	LT	1.5	14	8	24.4
57+47.60	57+57.60	RT	1.5	14	8	24.4
TOTAL						1330.0
USE						1330

BOX CULVERT EXTENSION SCHEDULE

STATION	SIDE	50102400	54003000	54002020	50800105
		CONCRETE REMOVAL	CONCRETE BOX CULVERTS	EXPANSION BOLTS 3/4 INCH	REINFORCEMENT BARS
		CU YD	CU YD	EACH	POUND
IL 57					
31+17.0	LT	3.0	20.12	16	3640
31+17.0	RT	3.0	24.06	16	4550
TOTALS		6.0	44.18	32	8190
USE		6.0	44.2	32	8190

ESTIMATED QUANTITIES

PAY ITEM NUMBER	PAY ITEM	UNIT	QUANTITY	LOCATION/REASON
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	100	FACILITATE DRAINAGE (AS NEEDED)
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	100	FACILITATE DRAINAGE (AS NEEDED)
20100500	TREE REMOVAL, ACRES	ACRE	0.5	FACILITATE DRAINAGE (AS NEEDED)
20200200	ROCK EXCAVATION	CU YD	300	AS DIRECTED
20300100	CHANNEL EXCAVATION	CU YD	500	FACILITATE DRAINAGE (AS NEEDED)
25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	1000	EROSION CONTROL (AS NEEDED)
28000500	INLET AND PIPE PROTECTION	EACH	25	EROSION CONTROL (AS NEEDED)
28001000	AGGREGATE (EROSION CONTROL)	TON	300	EROSION CONTROL (AS NEEDED)
40600990	TEMPORARY RAMP	SQ YD	170	FAI 172 RESURFACING (AS NEEDED)
44004250	PAVED SHOULDER REMOVAL	SQ YD	500	AS DIRECTED
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	250	AS DIRECTED
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	500	AS DIRECTED
63500105	DELINEATORS	EACH	590	AS DIRECTED TO CONTRACT 72694 SECTION
63500120	DELINEATOR REMOVAL	EACH	900	REMOVE ALL INCLUDING CONTRACT 72694 SECTION
66502405	WOVEN WIRE FENCE REMOVAL AND REPLACEMENT	FOOT	600	AS NEEDED FOR PLACING RIPRAP
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	PATCHING & WIDENING
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	RAMP CLOSURES
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	38000	TEMPORARY STRIPING ON BINDER/SURFACE
70300210	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	382	TEMPORARY STRIPING ON BINDER/SURFACE
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	265395	TEMPORARY STRIPING ON BINDER/SURFACE
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1174	TEMPORARY STRIPING ON BINDER/SURFACE
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	7396	TEMPORARY STRIPING ON BINDER/SURFACE
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1445	TEMPORARY STRIPING ON BINDER/SURFACE
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	144	TEMPORARY STRIPING ON BINDER/SURFACE
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	124547	REMOVE TEMPORARY STRIPING
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	650	UNDERDRAIN OUTLET LOCATIONS
78300100	PAVEMENT MARKING REMOVAL	SQ FT	5000	FAI 172 STRUCTURE REPAIRS (TRAFFIC CONTROL)
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1662	REMOVE ALL
X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	325	JOBSITE WHEN NEEDED
X0320887	POLYMER CONCRETE	CU FT	90	SURFACING OVER WIDE FLANGE BEAM TERMINAL JOINTS
X2503000	MAINTENANCE MOWING	ACRE	375	JOBSITE WHEN NEEDED