

STRIPING SCHEDULE

STATION TO STATION	SIDE	DESCRIPTION	URETHANE PAVEMENT MARKING			PREFORMED PLASTIC, TYPE B - INLAID							
			5"	5"	6"	LETTERS	5"	6"	8"	12"	12"	24"	
			WHITE	YELLOW	WHITE	SYMBOLS	WHITE	WHITE	WHITE	WHITE	YELLOW	WHITE	
			FOOT			SQ FT	FOOT						
FAI 172													
16+40.03	285+95.95	LT IS	EDGE LINE		26955.9								
0+00.00	197+82.00	LT IS	EDGE LINE		19782.0								
30+87.58	75+99.00	LT IS	EDGE LINE		4511.4								
76+00.00	285+95.95	RT IS	EDGE LINE		20996.0								
0+00.00	197+82.00	RT IS	EDGE LINE		19782.0								
30+87.58	79+00.00	RT IS	EDGE LINE		4812.4								
16+40.03	91+66.22	LT OS	EDGE LINE	7526.2									
91+66.22	94+16.51	LT OS	CHANNELIZATION				64.0						
94+16.51	96+81.12	LT OS	CHANNELIZATION					264.6					
96+81.12	115+69.01	LT OS	EDGE LINE	1887.9									
115+69.01	119+43.66	LT OS	CHANNELIZATION						374.7	204.0			
122+25.00	285+95.95	LT OS	EDGE LINE	16371.0									
0+00.00	197+82.00	LT OS	EDGE LINE	19782.0									
30+87.58	33+74.94	LT OS	EDGE LINE	287.4									
41+24.36	45+37.19	LT OS	CHANNELIZATION						412.8				
45+37.19	68+65.00	LT OS	EDGE LINE	2327.8									
68+65.00	72+37.51	LT OS	CHANNELIZATION										
72+37.51	75+24.02	LT OS	CHANNELIZATION						72.0				
75+24.02	75+99.00	LT OS	EDGE LINE	75.0									
76+00.00	92+43.71	RT OS	EDGE LINE	1643.7									
92+43.71	95+24.80	RT OS	CHANNELIZATION										
95+24.80	99+25.13	RT OS	CHANNELIZATION										
99+25.13	116+14.48	RT OS	EDGE LINE	1689.4									
116+14.48	120+24.58	RT OS	CHANNELIZATION										
127+74.79	285+95.95	RT OS	EDGE LINE	15821.2									
0+00.00	197+82.00	RT OS	EDGE LINE	19782.0									
30+87.58	37+00.33	RT OS	EDGE LINE	612.8									
39+84.49	43+62.86	RT OS	CHANNELIZATION						378.4	207.0			
43+62.86	66+76.11	RT OS	EDGE LINE	2313.3									
66+76.11	70+85.55	RT OS	CHANNELIZATION										
78+25.08	79+00.00	RT OS	EDGE LINE	74.9									
16+40.03	285+95.95	LT CL	SKIP-DASH					6740.0					
0+00.00	197+82.00	LT CL	SKIP-DASH					4950.0					
30+87.58	75+99.00	LT CL	SKIP-DASH					1130.0					
76+00.00	285+95.95	RT CL	SKIP-DASH					5250.0					
0+00.00	197+82.00	RT CL	SKIP-DASH					4950.0					
30+87.58	79+00.00	RT CL	SKIP-DASH					1210.0					
SUB-TOTALS				90194.3	96839.7	0.0	0.0	24230.0	208.0	3022.8	837.0	0.0	0.0

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
e:\pwwork\pwidot\LAUGHLINRL\0182983\009-D672A09-shi-schedule0.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0002' / IN.		CHECKED -	REVISED -
PLOT DATE = Feb-01-2010 09:34:03AM		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: none SHEET NO. 9 OF 18 SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	1-(1,2,3,4,5)RS	ADAMS	165	17
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72A09	