

PAVEMENT PATCHING CLASS A SCHEDULE

PATCH NUMBER	STATION	LOCATION	LENGTH	WIDTH	44200541	44200545	44200547	44213200	44213000	44213000	Z0075300
					TYPE II	TYPE III	TYPE IV	SAW	PATCHING	TIE	
					9 INCH	9 INCH	9 INCH	CUTS	REINFORCEMENT	BARS	
					SQ YD	SQ YD	SQ YD	FOOT	SQ YD	EACH	
FAI 172 (NORTHBOUND)											
1	79+50	DL	5.0	12	6.7				58.0	6.7	
2	80+18	DL	5.0	12	6.7				58.0	6.7	
3	102+18	DL	5.0	12	6.7				58.0	6.7	
4	107+81	DL	5.0	12	6.7				58.0	6.7	
5	108+53	DL	5.0	12	6.7				58.0	6.7	
6	110+08	DL	5.4	12	7.2				58.8	7.2	
7	110+57	DL	6.0	12	8.0				60.0	8.0	
8	110+95	DL	13.1	12		17.5			74.2	17.5	
9	111+43	DL	14.3	12		19.1			76.6	19.1	
10	131+10	DL	19.6	12			26.1		87.2	26.1	
11	147+67	DL	53.1	12			70.8		154.2	70.8	26
12	148+37	DL	29.4	12			39.2		106.8	39.2	14
13	149+88	DL	24.2	12			32.3		96.4	32.3	11
14	153+50	DL	26.5	12			35.3		101.0	35.3	12
15	153+79	DL	12.4	12		16.5			72.8	16.5	
16	154+08	DL	8.1	12	10.8				64.2	10.8	
17	154+16	PL	5.0	12	6.7				58.0	6.7	
18	154+50	PL	5.0	12	6.7				58.0	6.7	
19	158+83	DL	6.0	12	8.0				60.0	8.0	
20	159+10	DL	5.0	12	6.7				58.0	6.7	
21	161+03	DL	5.0	12	6.7				58.0	6.7	
22	164+03	DL	10.0	12	13.3				68.0	13.3	
23	166+10	DL	6.5	12	8.7				61.0	8.7	
24	166+87	DL	7.0	12	9.3				62.0	9.3	
25	168+63	DL	8.0	12	10.7				64.0	10.7	
26	170+82	DL	6.3	12	8.4				60.6	8.4	
27	178+26	DL	7.1	12	9.5				62.2	9.5	
28	178+64	DL	14.8	12		19.7			77.6	19.7	
29	183+15	DL	18.5	12		24.7			85.0	24.7	
30	186+82	DL	13.5	12		18.0			75.0	18.0	
31	214+09	DL	5.4	12	7.2				58.8	7.2	
32	268+53	DL	7.0	12	9.3				62.0	9.3	
STATION EQUATION 285+95.95 BK = 0+00 AH											
33	13+80	DL	5.0	12	6.7				58.0	6.7	
34	18+50	DL	5.5	12	7.3				59.0	7.3	
35	46+50	DL	5.0	12	6.7				58.0	6.7	
36	49+68	DL	5.0	12	6.7				58.0	6.7	
37	60+10	DL	7.5	12	10.0				63.0	10.0	
38	95+90	DL	5.0	12	6.7				58.0	6.7	
39	100+58	DL	5.0	12	6.7				58.0	6.7	
40	103+13	DL	6.5	12	8.7				61.0	8.7	
41	103+80	DL	5.0	12	6.7				58.0	6.7	
42	106+60	DL	5.0	12	6.7				58.0	6.7	
43	107+64	DL	5.0	12	6.7				58.0	6.7	
44	108+08	DL	5.0	12	6.7				58.0	6.7	
45	112+08	DL	6.0	12	8.0				60.0	8.0	
46	116+41	DL	5.0	12	6.7				58.0	6.7	
47	116+86	DL	5.5	12	7.3				59.0	7.3	
48	119+80	DL	5.5	12	7.3				59.0	7.3	
49	122+10	DL	5.0	12	6.7				58.0	6.7	
50	122+40	DL	5.0	12	6.7				58.0	6.7	
51	123+28	DL	13.4	12		17.9			74.8	17.9	
52	172+75	DL	6.0	12	8.0				60.0	8.0	
53	176+83	DL	8.6	12	11.5				65.2	11.5	
54	188+85	DL	8.5	12	11.3				65.0	11.3	
55	189+28	DL	5.0	12	6.7				58.0	6.7	
56	189+47	DL	5.0	12	6.7				58.0	6.7	
57	194+14	DL	10.1	12	13.5				68.2	13.5	
58	194+55	DL	5.0	12	6.7				58.0	6.7	
59	194+82	DL	5.6	12	7.5				59.2	7.5	
60	196+92	DL	6.4	12	8.5				60.8	8.5	
61	197+34	DL	5.0	12	6.7				58.0	6.7	
STATION EQUATION 197+82 BK = 30+87.58 AH											
62	31+00	DL	5.0	12	6.7				58.0	6.7	
63	32+17	DL	5.0	12	6.7				58.0	6.7	
64	32+74	DL	5.0	12	6.7				58.0	6.7	
65	33+18	DL	5.0	12	6.7				58.0	6.7	
66	37+26	DL	6.8	12	9.1				61.6	9.1	
67	39+86	DL	5.0	12	6.7				58.0	6.7	
68	42+65	DL	8.1	12	10.8				64.2	10.8	
69	43+01	DL	7.3	12	9.7				62.6	9.7	
70	55+94	DL	6.2	12	8.3				60.4	8.3	
71	65+89	DL	22.5	12			30.0		93.0	30.0	10
TOTALS					458.2	133.4	233.7	4644.4	825.3	73	
USE					459	134	234	4645	826	73	

FILE NAME = USER NAME = laughlinr1
 e:\pwork\pwork\LAUGHLINRL\0182983\009-D672A09-sha-schedule0.dgn
 PLOT SCALE = 100.0002' / IN.
 PLOT DATE = Feb-01-2010 09:34:11AM

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 SCALE: none SHEET NO. 12 OF 18 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	1-(1,2,3,4,5)RS	ADAMS	165	20
CONTRACT NO. 72A09				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				