

PAVEMENT PATCHING CLASS A SCHEDULE

PATCH NUMBER	STATION	LOCATION	LENGTH	WIDTH	44200529	44200541	44200545	44200547	44213200	44213000	Z0075300
					TYPE II 8 INCH	TYPE II 9 INCH	TYPE III 9 INCH	TYPE IV 9 INCH	SAW CUTS	PATCHING REINFORCEMENT	TIE BARS
					SQ YD			FOOT	SQ YD	EACH	
FAI 172 (SOUTHBOUND)											
72	70+30	DL	5.0	12		6.7			58.0	6.7	
73	70+10	DL	5.0	12		6.7			58.0	6.7	
74	69+84	DL	7.5	12		10.0			63.0	10.0	
75	69+57	DL	5.4	12		7.2			58.8	7.2	
76	55+00	DL	5.0	12		6.7			58.0	6.7	
77	53+42	DL	5.0	12		6.7			58.0	6.7	
78	53+31	DL	5.0	12		6.7			58.0	6.7	
79	49+15	DL	5.0	12		6.7			58.0	6.7	
80	48+55	DL	12.6	12			16.8		73.2	16.8	
81	48+35	DL	5.0	12		6.7			58.0	6.7	
82	48+20	DL	5.0	12		6.7			58.0	6.7	
83	48+00	DL	5.0	12		6.7			58.0	6.7	
84	46+92	DL	5.0	12		6.7			58.0	6.7	
85	39+95	DL	5.0	12		6.7			58.0	6.7	
86	36+68	DL	5.0	12		6.7			58.0	6.7	
87	35+40	DL	5.0	12		6.7			58.0	6.7	
88	34+64	DL	5.0	12		6.7			58.0	6.7	
89	18+41	DL	6.0	12		8.0			60.0	8.0	
90	16+40	DL	5.0	12		6.7			58.0	6.7	
91	16+23	DL	5.5	12		7.3			59.0	7.3	
TOTALS					13.4	533.3	185.8	130.9	5564.4	863.4	47
USE					14	534	186	131	5565	864	47

PAVEMENT PATCHING CLASS A SCHEDULE

PATCH NUMBER	STATION	LOCATION	LENGTH	WIDTH	44200529	44200533	44200535	44213200	44213000	Z0075300
					TYPE II 8 INCH	TYPE III 8 INCH	TYPE IV 8 INCH	SAW CUTS	PATCHING REINFORCEMENT	TIE BARS
					SQ YD			FOOT	SQ YD	EACH
RAMPS (IL 57 INTERCHANGE)										
1	24+94	RAMP D	87.0	16			154.7	238.0	154.7	43
2	26+56	RAMP D	6.5	14	10.1			69.0	10.1	
3	26+96	RAMP D	17.0	13		24.6		86.0	24.6	
TOTALS					10.1	24.6	154.7	393.0	189.4	43
USE					11	25	155	393	190	43