

WIDE FLANGE BEAM TERMINAL JOINT REPAIR SCHEDULE

STATION	SIDE	LENGTH	WIDTH	20201200	31200100	44200541	44213200	44213000	50500505	Z0017202
				REM & DISP UNSUITABLE MATERIAL	STABILIZED SUB-BASE 4"	CLASS A PATCH TYPE II 9 INCH	SAW CUTS	PATCHING REINFORCEMENT	STUD SHEAR CONNECTORS	DOWEL BARS 1 1/2"
				CU YD	SQ YD	SQ YD	FOOT	SQ YD	EACH	EACH
FAI 172										
118+22	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
118+22	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
118+22	LT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
118+22	LT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
122+92	LT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
122+92	LT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
146+74	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
146+74	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
152+71	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
152+71	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
153+44	LT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
153+44	LT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
178+50	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
178+50	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
182+93	LT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
182+93	LT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
183+93	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
183+93	RT	10	12	0.7	6.7	13.3	12.0	13.3	11	11
TOTALS				13.3	120.0	240.0	180.0	240.0	198	198
USE				14	120	240	180	240	198	198

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
e:\pwork\pwidot\LAUGHLINRL\0182983\009-D672A09-sht-schedule0.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: none SHEET NO. 15 OF 18 SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	1-(1,2,3,4,5)RS	ADAMS	165	23
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72A09	