

CLASS A PATCHING SCHEDULE ( I-55)

LOCATION	LENGTH DL (FOOT)	LENGTH PL (FOOT)	WIDTH (FOOT)	CL A 12" TY II (SQ YD)	CL A 14" TY II (SQ YD)	CL A 14" TY III (SQ YD)	SAW CUTS (FOOT)	PATCH REINF (SQ YD)
SOUTHBOUND I-55								
STA 714+65	12.0		12.0			16.00	72.0	16.00
STA 723+90	6.0		12.0		8.00		60.0	8.00
STA 723+90		6.0	12.0		8.00		60.0	8.00
STA 781+70	6.0		12.0		8.00		60.0	8.00
STA 781+70		6.0	12.0		8.00		60.0	8.00
STA 807+00	10.0		12.0		13.33		68.0	13.33
STA 808+25	8.0		12.0		10.67		64.0	10.67
STA 169+65	6.0		12.0		8.00		60.0	8.00
STA 178+50	6.0		12.0		8.00		60.0	8.00
STA 186+50	8.0		12.0		10.67		64.0	10.67
STA 215+90	6.0		12.0		8.00		60.0	8.00
STA 234+60	6.0		12.0		8.00		60.0	8.00
NORTHBOUND I-55								
STA 727+50	10.0		12.0	13.33			68.0	13.33
STA 729+30	6.0		12.0	8.00			60.0	8.00
STA 741+10	6.0		12.0	8.00			60.0	8.00
STA 746+30	6.0		12.0	8.00			60.0	8.00
STA 185+60	6.0		12.0	8.00			60.0	8.00
TOTALS				45.33	98.67	16.00	1056.0	160.00

PAVEMENT PATCHING SCHEDULE - FAU 8136 (STAUNTON ROAD)

LOCATION	LENGTH DL (FOOT)	WIDTH (FOOT)	PAVT PATCH 11" TY II (SQ YD)
WESTBOUND FAU 8136 (STAUNTON ROAD)			
STA 106+00	6.0	12.0	8.00
STA 110+50 TURN LANE	6.0	12.0	8.00
STA 111+50 TURN LANE	6.0	12.0	8.00
STA 115+50	6.0	12.0	8.00
STA 119+20	6.0	12.0	8.00
STA 120+50	6.0	12.0	8.00
STA 121+44	6.0	12.0	8.00
STA 23+25	6.0	12.0	8.00
STA 25+20	6.0	12.0	8.00
STA 28+30	6.0	12.0	8.00
STA 29+50	6.0	12.0	8.00
STA 45+10	6.0	12.0	8.00
STA 46+00	6.0	12.0	8.00
STA 47+00	6.0	15.0	10.00
EASTBOUND FAU 8136 (STAUNTON ROAD)			
STA 106+50	6.0	12.0	8.00
STA 108+98	6.0	12.0	8.00
STA 109+50	6.0	12.0	8.00
STA 110+50	6.0	12.0	8.00
STA 111+50	6.0	12.0	8.00
STA 112+50	6.0	12.0	8.00
STA 115+50	6.0	12.0	8.00
STA 116+50	6.0	12.0	8.00
STA 117+50	6.0	12.0	8.00
STA 119+50	6.0	12.0	8.00
STA 120+50	6.0	12.0	8.00
STA 121+50	6.0	12.0	8.00
STA 23+25	6.0	12.0	8.00
STA 32+10	6.0	12.0	8.00
STA 38+89	6.0	12.0	8.00
TOTALS			234.00

CLASS B PATCHING SCHEDULE (EXIT 41- FAU 8136 STAUNTON ROAD)

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	CL B 10" TY I (SQ YD)	CL B 10" TY II (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)
FAU 8136 (STAUNTON ROAD) INTERCHANGE							
RAMP A							
STA 13+00	6.0	9.0		6.00	39.0	16	3
STA 13+00	6.0	7.0	4.67		33.0	12	
STA 21+00	6.0	9.0		6.00	39.0	16	3
STA 21+00	6.0	7.0	4.67		33.0	12	
STA 21+25	6.0	9.0		6.00	39.0	16	3
STA 21+25	6.0	7.0	4.67		33.0	12	
STA 21+25	6.0	9.0		6.00	39.0	16	3
STA 21+25	6.0	7.0	4.67		33.0	12	
RAMP B							
STA 0+50	10.0	9.0		10.00	47.0	16	5
STA 0+50	10.0	7.0		7.78	41.0	12	
STA 7+60	6.0	9.0		6.00	39.0	16	3
STA 7+60	6.0	7.0	4.67		33.0	12	
STA 8+60	6.0	9.0		6.00	39.0	16	3
STA 8+60	6.0	7.0	4.67		33.0	12	
STA 9+75	6.0	9.0		6.00	39.0	16	3
STA 9+75	6.0	7.0	4.67		33.0	12	
STA 13+50	6.0	9.0		6.00	39.0	16	3
STA 13+50	6.0	7.0	4.67		33.0	12	
STA 16+40	10.0	9.0		10.00	47.0	16	5
STA 16+40	10.0	7.0		7.78	41.0	12	
RAMP C							
STA 6+50	8.0	9.0		8.00	43.0	12	4
STA 6+50	8.0	7.0		6.22	37.0	16	
STA 8+25	8.0	9.0		8.00	43.0	12	4
STA 8+25	8.0	7.0		6.22	37.0	16	
STA 12+00	8.0	9.0		8.00	43.0	12	4
STA 12+00	8.0	7.0		6.22	37.0	16	
RAMP D							
STA 14+00	6.0	9.0		6.00	39.0	12	3
STA 14+00	6.0	7.0	4.67		33.0	16	
STA 16+00	6.0	9.0		6.00	39.0	12	3
STA 16+00	6.0	7.0	4.67		33.0	16	
TOTALS			46.70	138.22	1136.0	420	52

PATCHING SUMMARY

LOCATION	CL A 12" TY II (SQ YD)	CL A 14" TY II (SQ YD)	CL A 14" TY III (SQ YD)	CL B 10" TY I (SQ YD)	CL B 10" TY II (SQ YD)	PAVT PATCH 11" TY II (SQ YD)	PATCH REINF (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)
I-55 MAINLINE	45.33	98.67	16.00				160.00	1,056.0		0
FAU 8136 INTERCHANGE RAMP				46.70	138.22			1,136.0	420	52
FAU 8136 (STAUNTON ROAD)						234.00				
GRAND TOTAL	45	99	16	47	138	234	160	2,192	420	52

FILE NAME =	USER NAME = coxte	DESIGNED -	REVISED -
es:\pwork\pwork\COXTE\dms25312\0672480-schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Mar-23-2010 03:21:34PM		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	59RS-2, BR	MACOUPIN	100	22
ILLINOIS FED. AID PROJECT			CONTRACT NO. 72A60	