

URETHANE PAVEMENT MARKING LINE 5'

LOCATION		COLOR	LENGTH (FOOT)
I-55 NORTHBOUND			
STA 698+00 TO STA 790+46	OUTSIDE	WHITE	9,246
STA 801+84 TO STA 809+87	OUTSIDE	WHITE	803
STA 161+08 TO STA 179+47	OUTSIDE	WHITE	1,839
STA 184+96 TO STA 250+00	OUTSIDE	WHITE	6,504
STA 698+00 TO STA 809+87	MEDIAN	YELLOW	11,187
STA 161+08 TO STA 250+00	MEDIAN	YELLOW	8,892
I-55 SOUTHBOUND			
STA 698+00 TO STA 793+74	OUTSIDE	WHITE	9,574
STA 799+76 TO STA 809+87	OUTSIDE	WHITE	1,011
STA 161+08 TO STA 177+53	OUTSIDE	WHITE	1,645
STA 188+87 TO STA 250+00	OUTSIDE	WHITE	6,113
STA 698+00 TO STA 809+87	MEDIAN	YELLOW	11,187
STA 161+08 TO STA 250+00	MEDIAN	YELLOW	8,892
FAU 8136 (STAUNTON ROAD) RAMP A			
STA 0+00 TO STA 20+05	RT	WHITE	2,005
STA 20+05 TO STA 21+82	RT	WHITE	218
STA 5+95 TO STA 20+69	LT	YELLOW	1,474
STA 20+69 TO STA 21+82	LT	YELLOW	88
FAU 8136 (STAUNTON ROAD) RAMP B			
STA 0+23 TO STA 1+29	RT	WHITE	133
STA 1+29 TO STA 26+69	RT	WHITE	2,540
STA 0+23 TO STA 1+73	LT	YELLOW	160
STA 1+73 TO STA 15+38	LT	YELLOW	1,365
FAU 8136 (STAUNTON ROAD) RAMP C			
STA 0+00 TO STA 21+63	RT	WHITE	2,163
STA 21+63 TO STA 22+58	RT	WHITE	185
STA 5+49 TO STA 22+02	LT	YELLOW	1,653
STA 22+02 TO STA 22+58	LT	YELLOW	64
FAU 8136 (STAUNTON ROAD) RAMP D			
STA 0+23 TO STA 1+24	RT	WHITE	137
STA 1+24 TO STA 26+66	RT	WHITE	2,542
STA 0+23 TO STA 1+75	LT	YELLOW	161
STA 1+75 TO STA 15+15	LT	YELLOW	1,340
FAU 8136 (STAUNTON ROAD) EASTBOUND			
STA 105+66 TO STA 122+25	RT	WHITE	1,659
STA 21+10 TO STA 21+55	RT	WHITE	45
STA 22+27 TO STA 34+50	RT	WHITE	1,223
STA 34+50 TO STA 35+81	SIDE RD	WHITE	188
STA 35+81 TO STA 41+27	RT	WHITE	546
STA 42+38 TO STA 57+73	RT	WHITE	1,535
STA 59+47 TO STA 65+27	RT	WHITE	580
STA 65+27 TO STA 66+71	SIDE RD	WHITE	199
STA 66+71 TO STA 76+85	RT	WHITE	1,014
FAU 8136 (STAUNTON ROAD) WESTBOUND			
STA 105+66 TO STA 122+25	LT	WHITE	1,659
STA 21+10 TO STA 21+21	LT	WHITE	11
STA 22+40 TO STA 40+83	LT	WHITE	1,843
STA 42+36 TO STA 57+60	LT	WHITE	1,524
STA 58+81 TO STA 64+57	LT	WHITE	576
STA 64+57 TO STA 67+15	SIDE RD	WHITE	413
STA 67+15 TO STA 76+85	LT	WHITE	970
FAU 8136 (STAUNTON ROAD) CENTERLINE			
STA 105+66 TO STA 115+08	CL	YELLOW	1,178
STA 115+08 TO STA 122+25	CL	YELLOW	1,434
STA 21+10 TO STA 27+60	CL	YELLOW	1,300
STA 27+60 TO STA 30+87	CL	YELLOW	1,308
STA 30+87 TO STA 31+73	CL	YELLOW	258
STA 31+73 TO STA 34+80	CL	YELLOW	614
STA 35+40 TO STA 42+08	CL	YELLOW	1,336
STA 42+98 TO STA 57+06	CL	YELLOW	2,816
STA 57+97 TO STA 65+69	CL	YELLOW	1,544
STA 66+30 TO STA 68+88	CL	YELLOW	516
STA 68+88 TO STA 70+42	CL	YELLOW	462
STA 70+42 TO STA 73+04	CL	YELLOW	1,048
STA 73+04 TO STA 76+85	CL	YELLOW	572
TOTAL			121,491

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5'

LOCATION	LENGTH (FEET)
I-55 MAINLINE	
NORTHBOUND	
STA 698+00 TO STA 809+87	2,800
STA 161+08 TO STA 250+00	2,230
SOUTHBOUND	
STA 698+00 TO STA 809+87	2,800
STA 161+08 TO STA 250+00	2,230
TOTAL	10,060

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24'

LOCATION	LENGTH (FEET)
FAU 8136 (STAUNTON ROAD) RAMP A	
STA 21+35 LT STOP BAR	18
STA 21+50 RT STOP BAR	18
RAMP C	
STA 22+40 LT STOP BAR	18
STA 22+45 RT STOP BAR	18
WEST FRONTAGE ROAD	
STA 150+36 LT STOP BAR	22
EAST FRONTAGE ROAD	
STA 172+90 RT STOP BAR	18
STA 172+95 RT STOP BAR	13
STA 157+45 LT STOP BAR	24
TOTAL	149

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS

LOCATION	QUANTITY (SQ FT)
FAU 8136 (STAUNTON ROAD)	
EASTBOUND	
STA 54+37 LEFT TURN ARROW	15.6
STA 55+17 LEFT TURN ARROW	15.6
STA 55+92 LEFT TURN ARROW	15.6
STA 56+77 LEFT TURN ARROW	15.6
WESTBOUND	
STA 43+33 LEFT TURN ARROW	15.6
STA 44+08 LEFT TURN ARROW	15.6
STA 44+93 LEFT TURN ARROW	15.6
STA 45+80 LEFT TURN ARROW	15.6
TOTAL	124.8

URETHANE PAVEMENT MARKING LINE 8''

LOCATION	LENGTH (FOOT)
FAU 8136 (STAUNTON ROAD) RAMP A	
STA 21+40 ISLAND	181
RAMP C	
STA 22+40 ISLAND	185
FAU 8136 (STAUNTON ROAD)	
STA 65+75 ISLAND (AT E FRONTAGE RD)	173
TOTAL	539

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8''

LOCATION	LENGTH (FEET)
FAU 8136 (STAUNTON ROAD) RAMP A	
STA 3+07 TO STA 5+95 (RAMP STATIONING) GORE AREA	288
STA 796+85 TO STA 799+76 (I-55 STATIONING) GORE AREA	291
STA 19+55 (WRONG WAY ARROW)	36.5
STA 20+52 (WRONG WAY ARROW)	36.5
RAMP B	
STA 15+38 TO STA 19+46 (RAMP STATIONING) GORE AREA	408
STA 177+53 TO STA 181+63 (I-55 STATIONING) GORE AREA	410
RAMP C	
STA 3+03 TO STA 5+49 (RAMP STATIONING) GORE AREA	246
STA 179+47 TO STA 181+93 (I-55 STATIONING) GORE AREA	246
STA 20+63 (WRONG WAY ARROW)	36.5
STA 21+83 (WRONG WAY ARROW)	36.5
RAMP D	
STA 15+15 TO STA 18+24 (RAMP STATIONING) GORE AREA	309
STA 798+78 TO STA 801+84 (I-55 STATIONING) GORE AREA	306
TOTAL	2,650

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6''

LOCATION	LENGTH (FOOT)
FAU 8136 (STAUNTON ROAD)	
EASTBOUND	
STA 54+35 TO STA 57+06 LEFT TURN LANE	271
WESTBOUND	
STA 42+98 TO STA 45+91 LEFT TURN LANE	293
RAMP A	
STA 793+73 TO STA 796+85 I-55 STATIONING	78
RAMP B	
STA 181+63 TO STA 188+87 I-55 STATIONING	181
RAMP C	
STA 181+93 TO STA 184+96 I-55 STATIONING	76
RAMP D	
STA 790+46 TO STA 798+78 I-55 STATIONING	208
TOTAL	1,107

PREFORMED PAVEMENT MARKING LINE 12''

LOCATION	LENGTH (FOOT)
FAU 8136 (STAUNTON ROAD) RAMP A	
STA 796+85 TO STA 799+76 (I-55 STATIONING) GORE AREA	83
RAMP C	
STA 179+47 TO STA 181+93 (I-55 STATIONING) GORE AREA	105
TOTAL	188

URETHANE PAVEMENT MARKING LINE 12''

LOCATION	LENGTH (FOOT)
FAU 8136 (STAUNTON ROAD) RAMP A	
STA 21+40 ISLAND	212
RAMP C	
STA 22+40 ISLAND	225
FAU 8136 (STAUNTON ROAD)	
EASTBOUND	
STA 27+60 TO STA 31+73 MEDIAN	131
WESTBOUND	
STA 65+75 (E FRONTAGE RD) ISLAND	73
STA 68+88 TO STA 73+04 MEDIAN	112
TOTAL	753