

RESURFACING SCHEDULE

STATION TO STATION	LENGTH FOOT	AVERAGE PAVEMENT WIDTH FOOT	AREA SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2" SQ YD	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 TON	AGGREGATE SHOULDERS, TYPE B TON	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT SQ YD	TEMPORARY RAMP SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" SQ YD
241+50.00 TO 241+80.00	30.0	27.0	90.0	0.0	9.0	0.2	7.6	1.3	90.0	15.0	0.0
241+80.00 TO 266+40.00	2460.0	27.0	7380.0	7380.0	738.0	14.8	619.9	105.1	0.0	0.0	0.0
266+40.00 TO 267+20.00	80.0	27.0	240.0	0.0	24.0	0.5	20.2	3.4	0.0	0.0	0.0
267+20.00 TO 275+15.00	795.0	27.0	2385.0	0.0	238.5	4.8	200.3	0.0	0.0	0.0	2385.0
275+15.00 TO 278+83.00	368.0	32.0	1308.4	0.0	130.8	2.6	109.9	0.0	0.0	0.0	1308.4
278+83.00 TO 279+49.00	66.0	27.0	198.0	0.0	19.8	0.4	16.6	0.0	0.0	0.0	198.0
279+49.00 TO 282+29.00	280.0	33.0	1026.7	0.0	102.7	2.1	86.2	0.0	0.0	0.0	1026.7
282+29.00 TO 295+60.00	1331.0	27.0	3993.0	0.0	399.3	8.0	335.4	0.0	0.0	0.0	3993.0
295+60.00 TO 296+40.00	80.0	27.0	240.0	0.0	24.0	0.5	20.2	3.4	0.0	0.0	0.0
296+40.00 TO 530+00.00	23360.0	27.0	70080.0	70080.0	7008.0	140.2	5886.7	997.7	0.0	0.0	0.0
530+00.00 TO 549+08.00	1908.0	26.0	5512.0	5512.0	551.2	11.0	463.0	81.5	0.0	0.0	0.0
549+08.00 TO 549+88.00	80.0	26.0	231.1	0.0	23.1	0.5	19.4	3.4	0.0	0.0	0.0
549+88.00 TO 564+74.00	1486.0	24.0	3962.7	0.0	396.3	7.9	332.9	0.0	0.0	0.0	3962.7
564+74.00 TO 565+54.00	80.0	26.0	231.1	0.0	23.1	0.5	19.4	3.4	0.0	0.0	0.0
565+54.00 TO 579+49.00	1395.0	26.0	4030.0	4030.0	403.0	8.1	338.5	59.6	0.0	0.0	0.0
579+49.00 TO 579+79.00	30.0	26.0	86.7	0.0	8.7	0.2	7.3	1.3	86.7	14.4	0.0
579+79.00 TO 581+51.00	172.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
581+51.00 TO 584+87.00	336.0	26.0	970.7	0.0	97.1	1.9	81.5	0.0	0.0	14.4	970.7
584+87.00 TO 596+50.00	1163.0	24.0	3101.3	0.0	310.1	6.2	260.5	0.0	0.0	0.0	3101.3
596+50.00 TO 597+30.00	80.0	26.0	231.1	0.0	23.1	0.5	19.4	3.4	0.0	0.0	0.0
597+30.00 TO 606+17.00	887.0	26.0	2562.4	2562.4	256.2	5.1	215.2	37.9	0.0	0.0	0.0
606+17.00 TO 623+02.00	1685.0	26.0	4867.8	4867.8	486.8	9.7	408.9	72.0	0.0	0.0	0.0
623+02.00 TO 623+82.00	80.0	26.0	231.1	0.0	23.1	0.5	19.4	3.4	0.0	0.0	0.0
623+82.00 TO 646+10.00	2228.0	24.0	5941.3	0.0	594.1	12.9	540.7	0.0	0.0	0.0	5941.3
646+10.00 TO 646+90.00	80.0	26.0	231.1	0.0	23.1	0.4	17.9	3.4	0.0	0.0	0.0
646+90.00 TO 696+50.00	4960.0	26.0	14328.9	14328.9	1432.9	28.7	1203.6	211.8	0.0	0.0	0.0
696+50.00 TO 725+50.00	2900.0	26.0	8377.8	8377.8	837.8	16.8	703.7	123.9	0.0	0.0	0.0
725+50.00 TO 725+80.00	30.0	26.0	86.7	0.0	8.7	0.2	7.3	1.3	86.7	14.4	0.0
TOTALS	48430.0		141925.0	117139.0	14193.0	285.0	11962.0	1717.0	263.0	58.0	22887.0

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH FOOT	PAINT PAVEMENT MARKING - LINE 4" FOOT	SHORT-TERM PAVEMENT MARKING FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	RAISED REFLECTIVE PAVEMENT MARKER EACH
241+50.00 TO 579+79.00	33829.0	79058.3	6768.0	1128.0	423.0
579+79.00 TO 581+51.00	172.0	387.0	32.0	5.3	0.0
581+51.00 TO 606+17.00	2466.0	5548.5	496.0	82.7	31.0
606+17.00 TO 696+50.00	9033.0	23426.3	1808.0	301.3	113.0
696+50.00 TO 725+80.00	2930.0	6592.5	584.0	97.3	37.0
TOTALS		115013.0	9688.0	1615.0	604.0

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>			F.A.S. RTE. 2701	SECTION (103.104)RS-4	COUNTY *	TOTAL SHEETS	SHEET NO. 7
et:\pwwork\pwwork\teasleyck\08150346\07	4134-sht-schedules.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 74134	
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							
	PLOT DATE = 1/25/2010	DATE -	REVISED -		* Effingham, Fayette, & Clay							