



Note: Seal back face of beam, top of beam, ends of beam, and front face of beam with Protective Coating - Concrete Bents and Piers (Epoxy). For location of Sections A-A, B-B, C-C, D-D, E-E, F-F, G-G, and additional notes, see Sheet No. 38.

Item	Quantity
Drilled Shafts (6 ft. 6 in. Dia.)	linear foot 217.0
Rock Sockets (6 ft. 0 in. Dia.)	linear foot 35.0
Supplementary Television Camera Inspection	each 1
Foundation Inspection Holes	linear foot 55.0
Sonic Logging Testing	each 2
Class B Concrete (Substructure)	cu. yard 235.7
Reinforcing Steel (Bridges)	pound 155,200
Mechanical Bar Splice	each 220
Reinforcing Steel (Epoxy Coated)	pound 48,600
Non-Special Waste Disposal	cu. yard 26.2

Note: These quantities are included in the estimated quantities table on Sheet No. 7.

PIER 23 EB - DETAILS