

## GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR AND ENGINEER SHALL BE AWARE THAT NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING AND TOPO SHOWN IN THE PLANS WAS CREATED USING MICROFILM AND FIELD MEASUREMENTS BY DESIGN PERSONNEL. BOTH SHALL BE ASSUMED TO BE APPROXIMATE.
3. EXCESS BITUMEN REMOVAL SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
4. MIXTURES FOR JOINTS, CRACKS, AND FLANGWAYS SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
5. THE USE OF VIBRATORY ROLLERS IS PROHIBITED IN RESIDENTIAL AREAS AND ON BRIDGES. THIS DOES NOT RELIEVE THE CONTRACTOR OF DENSITY REQUIREMENTS FOR THE BITUMINOUS PAVEMENTS AS SPECIFIED IN THE APPROPRIATE SECTIONS OF THE STANDARD SPECIFICATIONS.
6. THE THICKNESS OF THE HMA MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA MIXTURE IS PLACED.
7. THE THICKNESS OF HMA SURFACE REMOVAL IS THE REMOVAL DEPTH AT THE CENTERLINE. THE REMOVAL DEPTH VARIES FROM 3/4" TO 1". 1 1/2" SHALL BE REMOVED ON SN 061-0032. AN ESTIMATED 2700 TONS OF HMA SURFACE WILL BE REMOVED.
8. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

- \*AMERENIP, GAS & ELECTRIC
- \*AT&T COMMUNICATIONS
- \*CENTERPOINT ENERGY PIPELINE
- \*VILLAGE OF CENTRAL CITY SANITARY SEWER
- \*CITY OF CENTRALIA WATER & SANITARY SEWER
- \*CHARTER COMMUNICATIONS CABLE TV
- \*COUNTRYMARK COOPERATIVE, LLP PIPELINE
- \*FRONTIER COMMUNICATIONS COMPANY
- \*VILLAGE OF IRVINGTON WATER & SANITARY SEWER
- \*VILLAGE OF JUNCTION CITY WATER & SANITARY SEWER
- \*VILLAGE OF ODIN WATER & SANITARY SEWER
- \*PAETEC COMMUNICATIONS
- \*VILLAGE OF SANDOVAL WATER & SANITARY SEWER

MEMBERS OF J.U.L.I.E. (800)-892-0123 ARE INDICATED BY \*. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

9. ALL TEMPORARY PAVEMENT MARKINGS WILL BE PLACED IN SUCH A MANNER SO AS NOT TO INTERFERE WITH THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
10. HIGH EARLY STRENGTH CONCRETE MIX SHALL BE USED FOR THE CONSTRUCTION OF PCC ENTRANCES AND SIDE ROADS.
11. HIGH EARLY STRENGTH CONCRETE MIX SHALL BE USED FOR ALL PCC PATCHING.
12. ALL PATCHING ON THIS PROJECT SHALL BE COMPLETED PRIOR TO HMA SURFACE REMOVAL.
13. EXCEPT WHERE DESIGNATED OTHERWISE, THE LOCATIONS AND/OR DEPTHS OF UNDERGROUND UTILITIES SHOWN HAVE BEEN TAKEN FROM OFFICE RECORD INFORMATION FURNISHED BY THE UTILITY OWNERS AND MUST BE CONSIDERED APPROXIMATE.
14. THE CONTRACTOR SHALL BE AWARE THAT THERE ARE MANHOLES & VALVES LOCATED WITHIN THE RESURFACING LIMITS. CARE SHALL BE TAKEN IN THESE LOCATIONS DURING MILLING OPERATIONS.
15. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
16. THE PAVEMENT MARKING SHOWN IN THE PLANS IS APPROXIMATE. THE LOCATION OF THE PROPOSED PAVEMENT MARKINGS SHALL MATCH EXISTING FIELD CONDITIONS.
17. SHORT-TERM PAVEMENT MARKINGS SHALL BE APPLIED TO THE MILLED, PRIMED, HMA BINDER, AND HMA SURFACE. A QUANTITY FOR TEMPORARY PAVEMENT MARKING EQUAL TO THE AMOUNT OF PERMANENT PAVEMENT MARKING HAS BEEN ADDED TO THE PLANS. ONLY REMOVAL FROM THE FINAL SURFACE SHALL BE PAID FOR AS WORK ZONE PAVEMENT MARKING REMOVAL.
18. ANY EXISTING SIGNS THAT INTERFERE WITH THE REMOVAL OF EXISTING GUARDRAIL OR INSTALLATION OF NEW GUARDRAIL SHALL BE REMOVED AND RE-ERECTED AT THE SAME LOCATION. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF GUARDRAIL REMOVAL. SIGNS OR POSTS DAMAGED BY THE CONTRACTOR SHALL BE REPLACED AT CONTRACTOR'S EXPENSE.
19. FILTER FABRIC WILL BE REQUIRED UNDER THE PROPOSED RIP RAP CLASS A3.

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>	F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = #SCALE#	DRAWN - ---	REVISED - ---			*	(28,29)RS-4, 3ORS-1	MARION	21	3	
	PLOT DATE = #DATE#	CHECKED - ---	REVISED - ---			*	FAS 1791/FAU 8625/SBI 2C	CONTRACT NO. 76D78			
		DATE - -----	REVISED - ---			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					
						SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____					