

SUMMARY OF QUANTITIES

100% STATE

100% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION 1 1000	LOCATION 2 1000	-----
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25		
20400800	FURNISHED EXCAVATION	CU YD	350	200	150	
25000200	SEEDING, CLASS 2	ACRE	0.5	0.35	0.15	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	31	14	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	31	14	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	31	14	
25100115	MULCH, METHOD 2	ACRE	0.5	0.35	0.15	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	70	40	30	
28100105	STONE RIPRAP, CLASS A3	SQ YD	1222	1222		
28200200	FILTER FABRIC	SQ YD	1222	1222		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	67	63	4	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	10		10	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19.4	17.1	2.3	
40600300	AGGREGATE (PRIME COAT)	TON	92.1	81.7	10.4	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2534.7	2249.2	285.5	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1557.5	1102.5	455	
40600990	TEMPORARY RAMP	SQ YD	612.2	462.8	149.4	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	5079.2	4498.4	580.8	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	68.3	58.9	9.4	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	53553	53553		
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	6797.7		6797.7	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	117.8		117.8	
44000400	GUTTER REMOVAL	FOOT	1152	1102	50	
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	10.4		10.4	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	233.5	86.3	147.2	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	71	19.2	51.8	
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	242.1		242.1	
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	38	38		
44213200	SAW CUTS	FOOT	173	173		
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	1750	1750		
45200300	JOINT OR CRACK FILLING	POUND	497	497		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	650.4	562.3	88.1	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5.3	2.6	2.7	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION 1 1000	LOCATION 2 1000	-----
60602800	CONCRETE GUTTER, TYPE B	FOOT	1112	1102	10	
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1312.5	750	562.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	12	8	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	14	8	6	
63200310	GUARDRAIL REMOVAL	FOOT	871	813	58	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	4	2	
67100100	MOBILIZATION	L SUM	1	0.75	0.25	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.75	0.25	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.75	0.25	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.75	0.25	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7884	7884		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	54393	54393		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18611	18611		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	53861	53861		
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	532	532		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	245	245		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	33	20	13	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	14	8	6	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	245	245		
X7030070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	532	532		
Z0017202	DOWEL BARS 1 1/2"	EACH	69	69		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		

**Specialty Items*

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			*	(28,29)RS-4, 3ORS-1	MARION	21	5	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			* FAS 1791/FAU 8625/SBI 2C		CONTRACT NO. 76D78			
	PLOT DATE = #DATE#	DATE -	REVISED -			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			