

SUMMARY OF QUANTITIES

100% STATE

100% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 LOCATION #1	1000 LOCATION #2	1000 LOCATION #2
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	43.6	25.9	17	0.7
40600300	AGGREGATE (PRIME COAT)	TON	209	124	82	3
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	4953	2664	2249	40
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SG YD	1202	1202		
40600990	TEMPORARY RAMP	SG YD	563	200	363	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	8675	3995	4497	183
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	226	150	76	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SG YD	838		838	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SG YD	55621		53538	2083
44004250	PAVED SHOULDER REMOVAL	SG YD	8	8		
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SG YD	76		76	
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SG YD	70		70	
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SG YD	506		506	
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SG YD	150	150		
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SG YD	43	43		
44213100	PAVEMENT FABRIC	SG YD	652		652	
44213200	SAW CUTS	FOOT	245	245		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1661	1411	250	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	4943	4943		
50105220	PIPE CULVERT REMOVAL	FOOT	46		46	
50300225	CONCRETE STRUCTURES	CU YD	10.2	10.2		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1720	1720		
60100080	FRENCH DRAINS	CU YD	216		216	
60600605	CONCRETE CURB, TYPE B	FOOT	120	120		
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	6792.5	6792.5		
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4	4		
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	8		
63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	4	4		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	10	10		
63100217	TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	6500	6500		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 LOCATION #1	1000 LOCATION #2	1000 LOCATION #2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	4	3	
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	29830	7798	22032	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SG FT	692		692	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	98852	44095	54757	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2571	2571		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	823		823	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	324		324	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SG FT	39427	17462	21965	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SG FT	692		692	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	96912	42155	54757	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2571	2571		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	823		823	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	324		324	
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1940	1940		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	403	165	238	
78200300	PRISMATIC CURB REFLECTOR	EACH	170		170	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	70	70		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	20	20		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	403	165	238	
80300100	LOCATING UNDERGROUND CABLE	FOOT	30		30	

**Specialty Items*

FILE NAME =	USER NAME = watersle	DESIGNED -	REVISED -
ca:\pwork\PIWDOT\WATERSLE\d8175033\d8	6d83-eh-t-plan.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/15/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES		
SCALE:	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	DIST. 8 RESURF. 2010-5	MADISON	57	3
CONTRACT NO. 76083				
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT				