

GUARDRAIL SCHEDULE (NORTHBOUND)

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A FOOT	TRAFFIC BARRIER TERMINAL				GUARDRAIL MARKERS		TERMINAL MARKERS DIRECT APPLIED EACH	CONCRETE CURB, TYPE B FOOT
			TY 1, SPL (TAN) EACH	TYPE 2 EACH	TYPE 6 EACH	TYPE 6B EACH	AMBER EACH	SILVER EACH		
NORTHBOUND										
RT 113+62.50 TO 117+10.00	5509							5		
RT 113+58.25 TO 114+08.25			1					1	1	
RT 114+08.25 TO 116+45.75		237.5						3		
RT 116+45.75 TO 117+02.00						1		1		
RT 164+50.00 TO 173+27.00	877							11		
RT 164+50.00 TO 165+00.00			1					1	1	
RT 165+00.00 TO 173+31.25		831		1				11		
RT 235+59.00 TO 254+52.00	1893							24		38.8
RT 235+59.00 TO 236+05.25					1			1		
RT 236+05.25 TO 254+55.25		1850		1				24		
LT 231+22.00 TO 234+28.00	306						4			38.8
LT 229+98.50 TO 230+48.50			1				1		1	
LT 230+48.50 TO 233+79.75		331					5			
LT 233+79.75 TO 234+26.00					1		1			
RT 223+69.00 TO 234+28.00	1059							14		38.8
RT 223+67.25 TO 224+17.25			1					1	1	
RT 224+17.25 TO 233+79.75		963						13		
RT 233+79.75 TO 234+26.00					1			1		
RT 306+59.00 TO 310+09.00	350							5		
RT 309+42.25 TO 309+98.50						1		1		
RT 307+04.75 TO 309+42.25		238						3		
RT 306+54.75 TO 307+04.75			1					1	1	
NORTHBOUND TOTALS:	9,994	4,450	5	2	3	2	11	121	5	116

SEE SHEET 17 FOR ADDITIONAL QUANTITIES.

PROPOSED PATCHING SCHEDULE

NORTHBOUND LANES												
LOCATION STRUCTURE	WIDTH (FT)	LENGTH (FT)	AREA (SQ FT)	AREA (SQ YD)	TYPE	TOTALS				DOWEL BARS	TIE BARS	SAW CUTS
						I	II	III	IV			
041-0055	12	6	72	8.0	II	8.0				12.0	12	54
041-0001	12	6	72	8.0	II	8.0				12.0	12	54
041-0001	12	6	72	8.0	II	8.0				12.0	12	54
041-0001	12	6	72	8.0	II	8.0				12.0	12	54
041-0001	12	6	72	8.0	II	8.0				12.0	12	54
041-0001	12	6	72	8.0	II	8.0				12.0	12	54
041-0001	12	10	120	13.3	II	13.3				12.0	12	66
041-0054	12	8	96	10.7	II	10.7				12.0	12	60
041-0054	12	8	96	10.7	II	10.7				12.0	12	60
041-0054	12	6	72	8.0	II	8.0				12.0	12	54
041-0054	12	6	72	8.0	II	8.0				12.0	12	54
NORTHBOUND TOTALS:						98.7				132	132	618
SOUTHBOUND LANES												
LOCATION STRUCTURE	WIDTH (FT)	LENGTH (FT)	AREA (SQ FT)	AREA (SQ YD)	TYPE	TOTALS				DOWEL BARS	TIE BARS	SAW CUTS
						I	II	III	IV			
041-0054	12	6	72	8.0	II	8.0				12.0	12	54
041-0002	12	6	72	8.0	II	8.0				12.0	12	54
041-0002	12	6	72	8.0	II	8.0				12.0	12	54
041-0002	12	6	72	8.0	II	8.0				12.0	12	54
041-0002	12	6	72	8.0	II	8.0				12.0	12	54
041-0002	12	6	72	8.0	II	8.0				12.0	12	54
041-0002	12	6	72	8.0	II	8.0				12.0	12	54
041-0002	12	6	72	8.0	II	8.0				12.0	12	54
041-0002	12	6	72	8.0	II	8.0				12.0	12	54
041-0002	12	7	84	9.3	II	9.3				12.0	12	57
041-0002	12	14	168	18.7	III	18.7				12.0	12	78
041-0055	12	8	96	10.7	II	10.7				12.0	12	60
SOUTHBOUND TOTALS:						100	19			156	156	735
JOB TOTALS:						199	19			288	288	1353