

### GRADING AND SHAPING SHOULDERS SCHEDULE

LOCATION STATION TO STATION	LENGTH	GRADING AND SHAPING SHOULDERS
NORTHBOUND	FEET	UNIT
13+00.0 TO 108+15.0	9515.00	190.30
RAMP "D"	632.00	12.64
RAMP "C"	536.00	10.72
108+15.0 TO 116+50.0	835.00	16.70
116+50.0 TO 117+43.0		NORTH AVENUE
117+43.0 TO 117+55.1	12.07	0.24
117+55.1 TO 117+62.1		STATION EQUATION
117+62.1 TO 234+22.7	11660.63	233.21
234+22.7 TO 235+62.4		STRUCTURES
235+62.4 TO 309+50.0	7387.60	147.75
309+50.0 TO 310+50.0		CAMPGROUND RD.
310+50.0 TO 375+40.0	6490.00	129.80
<b>SOUTHBOUND</b>		
13+00.0 TO 109+01.3	9601.30	192.03
RAMP "A"	374.00	7.48
RAMP "B"	464.00	9.28
109+01.3 TO 116+50.0	748.70	14.97
116+50.0 TO 117+43.0		NORTH AVENUE
117+43.0 TO 117+55.1	12.07	0.24
117+55.1 TO 117+62.1		STATION EQUATION
117+62.1 TO 234+22.7	11660.63	233.21
234+22.7 TO 235+62.4		STRUCTURES
235+62.4 TO 309+50.0	7387.60	147.75
309+50.0 TO 310+50.0		CAMPGROUND RD.
310+50.0 TO 375+40.0	6490.00	129.80
<b>TOTALS</b>		<b>1,477</b>

### DELINEATOR SCHEDULE

LOCATION STATION TO STATION	LENGTH	DELINEATORS
NORTHBOUND	FEET	EACH
12+90.0 TO 101+75.0	8885.00	23
101+75.0 TO 108+11.9	636.90	2
RAMP "D"		20
RAMP "C"		20
108+11.9 TO 125+61.0	1749.10	5
125+61.0 TO 137+33.0	1172.00	12
137+33.0 TO 234+22.7	9689.70	25
234+22.7 TO 235+62.4	139.70	STRUCTURE
235+62.4 TO 375+40.0	13977.60	35
<b>SOUTHBOUND</b>		
12+90.0 TO 98+96.1	8606.10	22
98+96.1 TO 109+01.0	1004.90	11
RAMP "A"		20
RAMP "B"		20
109+01.0 TO 125+61.0	1660.00	5
125+61.0 TO 132+27.6	666.60	7
132+27.6 TO 234+22.7	10195.10	26
234+22.7 TO 235+62.4	139.70	STRUCTURE
235+62.4 TO 375+40.0	13977.60	35
<b>TOTALS</b>		<b>288</b>

### SEEDING AND EROSION CONTROL SCHEDULE

STATION	LOCATION	SEEDING CLASS 2	SEEDING CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING
		ACRE	ACRE	POUND	POUND	POUND	TON	TON	SO YD	POUND
123+40.00	NORTHBOUND	0.20	0.20	36.0	18.0	18.0	0.40	0.4	220	40.0
123+40.00	SOUTHBOUND	0.20	0.20	36.0	24.0	24.0	0.40	0.4	220	40.0
<b>TOTALS</b>		<b>0.4</b>	<b>0.4</b>	<b>72.0</b>	<b>42.0</b>	<b>42.0</b>	<b>0.8</b>	<b>0.8</b>	<b>440.0</b>	<b>80.0</b>