

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	1000 URBAN						CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	1000 URBAN					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	14						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	944.2	944.2					
40600300	AGGREGATE (PRIME COAT)	TON	72	72						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6051	6051					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	5	5						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	190	190					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	411	411					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	758	758						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	235	235					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	40	40						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	141	141					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	29	29						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	261	261					
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	19	19						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1535	1535						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	766	766					
42001300	PROTECTIVE COAT	SQ YD	200	200						X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	592	592					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL. 2 1/4"	SQ YD	14338	14338						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	50	50					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600	600						Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	175	175															
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	3499	3499															
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	50	50															
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	125	125															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	27	27															
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	27	27															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3840	3840															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	944.2	944.2															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6051	6051															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	190	190															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	411	411															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	422	422															

\*Specialty Items