

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE
20201006	GRADING AND SHAPING SHOULDERS	UNIT	260	260	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1684	1684
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	53	53	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2804	2804
40600300	AGGREGATE (PRIME COAT)	TON	261	261	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	864	864
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	445	445	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	264	264
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	8771	8771	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	39398	39398
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1212	1212	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	619	619
42001300	PROTECTIVE COAT	SQ YD	1216	1216	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	104024	104024
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2734	2734	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1684	1684
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	119657	119657	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2804	2804
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	6840	6840	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	864	864
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	5983	5983	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	264	264
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	4188	4188	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	764	764
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	599	599	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	764	764
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1196	1196	88600600	DETECTOR LOOP REPLACEMENT	FOOT	388	388
60260100	INLETS TO BE ADJUSTED	EACH	2	2	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	437	437
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1	X0322729	MATERIAL TRANSFER DEVICE	TON	14412	14412
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1	X0656100	DRIVEWAY <sup>PAVEMENT</sup> REMOVAL AND REPLACEMENT	SQ YD	468	468
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	14412	14412
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	6604	6604
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	32955	32955	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	619	619					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	104024	104024					

**LONCO, INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY  
DRAWN - ST  
CHECKED - MJY  
DATE - 04/22/2009

REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**US ROUTE 41  
SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 3 OF 25 SHEETS STA. 421+00 TO STA. 580+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
346	(124 & 125) X-RS-5	LAKE	25	3
D-91-059-09			CONTRACT NO. 60F28	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				