



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

ARTERIAL ROAD INFORMATION SIGN

| | | | | | | | | | | |
|---|------------------------|----------------|-----------|--|--|---|--------------------|--------------------|--------------|-----------|
| LONCO, INC. CONSULTING ENGINEERS 1560 WALL ST., SUITE 222 NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100 | USER NAME = #USER# | DESIGNED - MJY | | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | US ROUTE 41 DISTRICT ONE DETAILS SHEETS | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | PLOT SCALE = \$SCALE\$ | CHECKED - MJY | REVISED - | | | 346 | (124 & 125) X-RS-5 | LAKE | 25 | 24 |
| PLOT DATE = \$DATE\$ | DATE - 04/22/2009 | REVISED - | | | | C-91-059-09 | | CONTRACT NO. 60F28 | | |
| | | | | SCALE: NONE SHEET NO. 23 OF 25 SHEETS STA. 421+00 TO STA. 580+00 | | FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT | | | | |