

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						CODE NO	ITEM	UNIT	TOTAL QUANTITIES							
			1000									1000							
20201006	GRADING AND SHAPING SHOULDERS	UNIT	392	392						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	48815	48815					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	35	35						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2685	2685					
40600300	AGGREGATE (PRIME COAT)	TON	177	177						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1008	1008					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	44	44						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	376	376					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	415	415					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	255	255						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	415	415					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7450	7450						* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1					
42001300	PROTECTIVE COAT	SQ YD	19	19						* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	650	650					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	88692	88692						* 87900200	DRILL EXISTING HANDHOLE	EACH	2	2					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	85	85						* 88500100	INDUCTIVE LOOP DETECTOR	EACH	2	2					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	269	269						* 88600100	DETECTOR LOOP, TYPE I	FOOT	62	62					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	60	60						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	728	728					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	160	160						* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	570	570					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1305	1305						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	3492	3492					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	14	14						Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	2	2					
60404210	FRAMES AND GRATES, TYPE 2	EACH	1	1															
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3348	3348															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	754	754															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	48815	48815															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2685	2685															
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1008	1008															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	376	376															
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	754	754															

*SPECIALTY ITEMS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FILE NAME =
c:\pwwork\pwwork\banks\dms89320\sh_rdwj.dgn

USER NAME = banks
DESIGNED -
DRAWN -
PLOT SCALE = 50,0000' / IN.
CHECKED -
PLOT DATE = 3/25/2009
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3778	(3143 & 3144) RS-1	COOK	29	3
CONTRACT NO. 60F44				

SCALE: SHEET NO. OF SHEETS STA. TO STA.

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT