

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	63	63
40600300	AGGREGATE (PRIME COAT)	TON	362	362
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	60	60
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,129	1,129
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	656	656
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7,594	7,594
42001300	PROTECTIVE COAT	SQ YD	4,699	4,699
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	100	100
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	90,405	90,405
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	463	463
44000600	SIDEWALK REMOVAL	SQ FT	100	100
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	20,176	20,176
44002000	CONCRETE CURB REMOVAL	FOOT	35	35
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	1,079	1,079
44002215	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 3/4"	SQ YD	3,125	3,125
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	20	20
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	75	75
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	85	85
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1,000	1,000
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	500	500
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	1,000	1,000
44213200	SAW CUTS	FOOT	364	364
55039700	STORM SEWERS TO BE CLEANED	FOOT	5,535	5,535
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	120	120
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	105	105
60404800	FRAMES AND GRATES, TYPE 11	EACH	6	6
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
60600805	CONCRETE CURB, TYPE B (DOWELLED)	FOOT	35	35
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,079	1,079
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	40,000	40,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,956	1,956
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	48,232	48,232
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,573	3,573
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,315	2,315
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	718	718
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,500	5,500
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,956	1,956
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	48,232	48,232
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,573	3,573
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,315	2,315
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	718	718
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,524	1,524
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,524	1,524
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,692	1,692
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	900	900
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,797	3,797
Z0017202	DOWEL BARS 1 1/2"	EACH	296	296
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	97	97
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEM

FILE NAME = D160F49-shr-S00.dgn
PLOT DATE = 3/31/2009

CR CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	M.P.	REVISED -	
DATE -	MARCH 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
WOLF ROAD (IL. 72 (TOUHY AVENUE) TO IL. 58 (GOLF ROAD))

SCALE: 1" = 50' SHEET NO. 1 OF 1 SHEETS STA. 101+00 TO STA. 252+03

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2691	3134 RS-3	COOK	33	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60F49	