

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
20200100	EARTH EXCAVATION	CU YD	150	150
20201006	GRADING AND SHAPING SHOULDERS	UNIT	110	110
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	35	35
35800200	AGGREGATE BASE REPAIR	TON	175	175
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	25	25
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	66	66
40600300	AGGREGATE (PRIME COAT)	TON	340	340
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	84	84
40600525	LEVELING BINDER (HAND METHOD), N50	TON	55	55
40600895	CONSTRUCTING TEST STRIP	EACH	4	4
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,770	1,770
40600990	TEMPORARY RAMP	SQ YD	1,940	1,940
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	390	390
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	31	31
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	7,300	7,300
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	83,400	83,400
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	215	215
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3,000	3,000
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2,220	2,220
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	120	120
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	820	820
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	510	510
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	480	480
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	220	220
55039700	STORM SEWERS TO BE CLEANED	FOOT	7,800	7,800
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	32	32

• DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	120	120
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9,300	9,300
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	500	500
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	76,500	76,500
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5,700	5,700
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	5,100	5,100
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,800	1,800
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	22,900	22,900
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	160	160
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	56,500	56,500
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,900	1,900
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,700	1,700
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	600	600
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	600	600
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	580	580
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	700	700
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4,600	4,600
X4400100	PORTLAND CEMENT CONCRETE REMOVAL (VARIABLE DEPTH) <u>(SURFACE)</u>	SQ YD	260	260
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	220	220

FILE NAME = N:\PROJ\3368\3368-12\Design\ProposedPlan\3368-12-03-Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel: 773.775.4009 Fax: 773.775.4014

USER NAME = alau	DESIGNED AL	REVISED -
	DRAWN RJR	REVISED -
PLOT SCALE = 1:8000' / IN.	CHECKED WBL	REVISED -
PLOT DATE = 4/8/2009	DATE 3/20/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WALKER AVENUE /SHERIDAN ROAD
LAKEVIEW AVE TO CENTRAL AVE & MULBERRY PL TO LAKE-COOK ROAD
SUMMARY OF QUANTITIES

SCALE: 1"=50' SHEET NO. 3 OF 26 SHEETS STA. TO STA.

F.A.U. RTE. 1251/2784	SECTION 2009-042 RS	COUNTY LAKE	TOTAL SHEETS 26	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 60G49	