

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE		CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	300	300		44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	400	400	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	20178	20178		44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2581	2581	
28000510	INLET FILTERS	EACH	52	52		44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	2688	2688	
35800100	PREPARATION OF BASE	SQ YD	520	520		44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	664	664	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	30	30		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	118272	118272	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	108.3	108.3		48101200	AGGREGATE SHOULDERS, TYPE B	TON	220	220	
40600300	AGGREGATE (PRIME COAT)	TON	48.8	48.8		48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1281	1281	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	83	83		55039700	STORM SEWERS TO BE CLEANED	FOOT	1730	1730	
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	5804	5804		60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	6	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		60255500	MANHOLES TO BE ADJUSTED	EACH	16	16	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4114	4114		60260100	INLETS TO BE ADJUSTED	EACH	2	2	
40600990	TEMPORARY RAMP	SQ YD	155	155		60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	22	22	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	4652	4652		60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	82	82	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	12317	12317		64200105	SHOULDER RUMBLE STRIP	FOOT	1200	1200	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	30	30		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
42001300	PROTECTIVE COAT	SQ YD	410	410		67100100	MOBILIZATION	L SUM	1	1	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	991	991		70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1526	1526		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	22	22	
42400800	DETECTABLE WARNINGS	SQ FT	60	60		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	10151	10151		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8360	8360	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	138172	138172		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1482.4	1482.4	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	392	392		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	95832	95832	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	6332	6332		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5720	5720	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	220	220	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	5933	5933							
44003900	MEDIAN SURFACE REMOVAL AND REPLACEMENT	SQ FT	5200	5200							



USER NAME = #USER#	DESIGNED - MJY	REVISIONS
DRAWN - RJG	CHECKED - MJY	DATE - 04/15/2009
PLLOT SCALE = #SCALE#		
PLLOT DATE = #DATE#		

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
IL ROUTE 25**

SCALE: NONE      SHEET NO. 3 OF 38 SHEETS      STA. 9+80 TO STA. 354+42

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2503	(53 & 54) RS-7	KANE	38	3
D-91-523-09		CONTRACT NO. 60667		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		